

SURVEY & REMONUMENTATION

MAY - 1 1995

LIBER 14833 PG 129 94 193373

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. SMITH

For corners in Oakland

	Located In:		Corner Code #
	5N	11E	
1. Public Land Survey	T	R	M-6
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

\$ 7.00 MISCELLANEOUS RECORDING
 \$ 2.00 REMONUMENTATION
 15 JUL 94 7:29 A.M. RECEIPT# 1A
 PAID RECORDED - OAKLAND COUNTY
 LYNN D. ALLEN, CLERK/REGISTER OF DEEDS
 Compliance with
 ACT 345, P.A. 1990

APPROVED ON: 2-2-94
 OAKLAND COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Bruce Antcliff, in a field survey on November 8, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

<p>F-5 GLO Post L.C.R.C. L. 636, P. 639 (1973) 5/8" Bar 23.05' SW to Form Nail in Disc in NNE Face of 22" Oak 36.33' NE to Form Nail in Disc in ESE Face of 32" Oak 44.02' NW to Form Nail in Disc in SW Face of 24" Oak</p>	<p>L.C.R.C. L. 9418, P. 92 (1986) 1/2" Iron Bar W/ Cap #14097 PK nail in 30" Oak - NW - 43.67' Nail & cap #5787 in 30" Oak - NNE - 36.33' Nail & cap #5787 in 30" Oak - ESE - 23.05' Survey L. 9418, P. 84 (1986) Same as L.C.R.C. L. 9418, P. 92</p>	<p>L.C.R.C. L. 10709, P. 790 (1988) 1/2 Iron Rod, Center of Dequindre Road N 40° W - 43.78 ft - PKW NE Side 31" Oak S 20° E - 71.35 ft - PKW East Side 19" Cherry S 35° W - 66.11 ft - PKW East Side 19" Cherry</p>
--	---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-5 Found capped 1/2" iron in the center line of Dequindre Road.
 Checks the following witnesses:

<p>L.C.R.C. L. 9418, P. 92 (1986) Nail & Cap #5787 in 30" Oak - ESE - 23.05' Survey L. 9418, P. 84 (1986) Same as L.C.R.C. L. 9418, P. 92</p>	<p>L.C.R.C. L. 10709, P. 790 (1988) S 35° W - 66.11 ft - PKW East Side 19" Cherry</p>
--	--


*700
 500
 file*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-5 The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Set 5/8" rebar with standard Oakland County cap.

- P.K. Nail and Brass Tag in SW face of 30" Oak - S 50° E - 22.38'
- P.K. Nail and Brass Tag in SW face of 26" Oak - S 10° E - 79.22'
- P.K. Nail and Brass Tag in E face of 18" Cherry - S 35° W - 65.95'
- chain link fence - East - 44.24'
- in center line of North and South road



Signed by Bruce Antcliff
 Surveyor's Michigan License No. 25826

Date 7-11-94