

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE, Filing Requirement of Act 74, Mich. P.A. 1970

7.00 MISCELLANEOUS RECORDING \$ 2.00 REMONUMENTATION

For corners in COMMISSION

2 FEB 95 7:26 A.M. RECEIPT# 2B PAID RECORDED - OAKLAND COUNTY LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Table with columns: Located in: Addison Township, Corner Code #. Rows for Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec.

OK - T. SMITH Compliance with ACT 345, P.A. 1990 APPROVED ON: 12-12-94 OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat Private Claims

I, Randy Kolehouse, in a field survey on July 20 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-7 Per G.L.O. notes, J. Wampler set a post in 1817.

- List of survey measurements and bearings: Recorded Survey L. 6609 P. 160 1975, L.C.R.C. L. 9248 P. 636 1985, J. Smith Survey 1990.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-7 Found 1/2" iron rod in C/L of Dequindre Road (gravel) running N-S and at C/L of Frick Road West (gravel) running West with a N-S fence 44' East and checked the following witnesses.

- Witness measurements: L.C.R.C. L. 9248 P. 636 1985, S 45° W 36.88' P.K. N Side 34' Oak, S 60° E 34.66' P.K. S Side 33" Oak, N 80° E 35.86' P.K. NE Side 17" Oak

J. Smith Measures 2661.60' to M-8

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-7 Set a 5/8" rebar with brass cap stamped "Oakland County Remonumentation P.S. #25854" in place of found 1/2" iron rod.

- Monument descriptions: PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in E. Side of E'ly Twin 8" Oak N 10° W 92.64', PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in N Side 34" Oak S 45° W 36.88', PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in S Side 33" Oak S 60° E 34.66', PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NE Side 17" Oak N 80° E 35.86'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J Kolehouse Date 12/23/94 Surveyor's Michigan License No. 25854

