

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For comers in

COMMISSION

Oakland (County)	Located in:	Addison Township	Corner Code #
1. Public Land Survey	T <u>5N</u>	R <u>11E</u>	<u>M-8</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

\$ 7.00 MISCELLANEOUS RECORDING  
\$ 2.00 REMONUMENTATION  
2 FEB 95 7:26 A.M. RECEIPT# 28  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS  
**OK - T. SMITH**  
Compliance with  
ACT 345, P.A. 1990  
APPROVED ON: 12-12-94  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on July 20 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-8 Per G.L.O. notes, J. Wampler set a post in 1817.

O.C.R.C. 1962 1" x 18" Iron Pin NW 54.5' Nail in 18" W. Oak SW 57.8' Nail in 36" Oak West 33.0' Fence	Barnes Survey 1977 1" Pinched Iron NW 56.40' P.K. in 30" Oak W 35.20' Tag #123 in Fence Cor. E 44.15' Fabric in 6' Ch. Lik. Fence	L.C.R.C. L. 8075 P. 760 1981 1" Pinched Pipe N 40° W 56.46 to P.K. 18" Oak W 36.52' Tag in Cor. Fence Post East 44.30' to Fence Wire	L.C.R.C. L. 9248 P. 636 1985 5/8" Iron Road S 80° W 57.88' P.K. SE Side 41" Oak N 40° W 56.54' P.K. NE Side 24" Oak N 50° E 75.96' N/W NW Side P. Pole S 10° E 110.05' Nail in 36" Oak
---	---	--	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-8 Found 5/8" iron rod 4.5' West of East Edge DeQuindre Road running N-S. Checks the following witnesses.

L.C.R.C. L. 9248 P. 636 1985  
S 80° W 57.94' P.K. SE Side 41" Oak  
N 40° W 56.58' P.K. NE Side 24" Oak  
N 50° E 75.92' N/W NW Side P. Pole

J. Smith Measures 2661.60' to M-7  
Kobs Measures 2678.27' to M-9

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-8 Set a 5/8" rebar with brass cap stamped "Oakland County Remonumentation P.S. #25854" in place of found 5/8" iron bar.

- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in W Side 40" Oak S 10° E 111.86'
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in N Side 24" Oak N 80° W 102.79'
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in SE Side 41" Oak S 80° W 57.94'
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NNE Side 24" Oak N 40° W 56.58'
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NW Side P. Pole N 50° E 75.92'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy Kolehouse Date 12/23/94  
Surveyor's Michigan License No. 25854

