

**SURVEY & REMONUMENTATION**

LIBER **15234** PG **554**

FEB 295020001

MAY - 1 1995

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

**COMMISSION**

For corners in	Located in:	Addison Township	Corner Code #
<u>Oakland</u> (County)			
1. Public Land Survey	T <u>5N</u> R <u>11E</u>		<u>M-9</u>
	T _____ R _____		_____
	T _____ R _____		_____
	T _____ R _____		_____
2. Property Controlling in Section	S _____ T _____	R _____	_____
	S _____ T _____	R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____	R _____	_____
	S _____ T _____	R _____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

\$ 7.00 MISCELLANEOUS RECORDING  
\$ 2.00 REMONUMENTATION  
2 FEB 95 7:26 A.M. RECEIPT# 28  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS  
**OK - T. SMITH**  
Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 12-12-94  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on July 20 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

M-9 Per G.L.O. notes, J. Wampler set a post in 1816 and 1817.

M.E. Baldwin Date N/A	O.C.R.C. 1962	L.C.R.C. L. 8010 P. 822 1981	Rec. Survey L. 9169 P. 218 1985	Record Survey L. 13425 P. 306 1992
Iron Post	1" Iron Pin	1/2" Iron	Nail w/Cap P. Pole NW 119.52'	Nail w/Cap P. Pole NW 119.52'
NE Stone Pillar 46.4'	NE Stone Pillar 46.4'	SW 65.56' to Nail in D.E. Pole	Nail w/Cap P. Pole SW 65.55'	Nail w/Cap P. Pole SW 65.55'
SE Nail in 24" Poplar 40.55'	SE Nail in 24" Poplar 40.55'	NW 118.00' to Spike & Washer	Nail w/Cap B.T.P. SE 36.03'	Nail w/Cap B.T.P. SE 36.03'
NW Nail in 18" Maple 55.8'	NW Nail in 18" Maple 55.8'	D.E. Pole	SW Cor. Top 1.7x1.7 Stone Post	SW Cor. Top 1.7x1.7 Stone Post
		NE 56.56' to Chain Link Fence Corner Post	NE 46.39'	NE 46.39'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

M-9 Found "T" iron 4.5' East of C/L DeQuindre Road (gravel) running N-S at C/L Mack Road (gravel) running E-W (corner shown common by Macomb Co. Witnesses L. 4055 P. 644). Checked witnesses as follows.

M.E. Baldwin Date N/A	L.C.R.C. L. 8010 P. 822 1981	Rec. Survey L. 9169 P. 218 1985	Record Survey L. 13425 P. 306 1992
N 48° E SW Cor. Stone Post at Top 46.62'	N 55° E Cor. Post Chain Link Fence 56.56'	Nail w/Cap P. Pole NW 119.52'	Nail w/Cap P. Pole NW 119.52'
	S 60° W Nail & Tag NW Side D.E. Pole 65.77'	Nail w/Cap P. Pole SW 65.55'	Nail w/Cap P. Pole SW 65.55'
	N 25° W Nail & Washer E Side D.E. Pole 118.14'	SW Cor. Top 1.7x1.7 Stone Post	SW Cor. Top 1.7x1.7 Stone Post
		NE 46.39'	NE 46.39'

Barnes Measures North to M-8 2679.28'  
Kobs & King Measures West to L-9 2691.18'  
Kobs & King Measures North to M-8 2678.68'

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

M-9 Set a 5/8" rebar with brass cap stamped "Oakland County Remonumentation P.S. #25854" in place of found 1/2" iron rod.

PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in W Side 15" Maple N 25° E 71.76'  
PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NW Side D.E. Pole S 60° W 65.77'  
PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in E Side D.E. Pole N 25° W 118.14'  
SW Cor. 1.7" Stone Post at Top N 48° E 46.62'  
Chain Link Fence Corner Post N 55° E 56.56'  
PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in W Side 18" Spruce S 37° E 82.51'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse  
Surveyor's Michigan License No. 25854

Date 12/23/94

