

MAY - 1 1995

LIBER 15234 PG 555

LAND CORNER RECORDATION CERTIFICATE, Filing Requirement of Act 74, Mich. P.A. 1970

7.00 MISCELLANEOUS RECORDING
2.00 REMONUMENTATION
2 FEB 95 7:26 A.M. RECEIPT# 2B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

OK - T. SMITH

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-12-94
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

For corners in

Table with columns: Located in: Addison Township, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec.

- 4. Lot No. Recorded Plat
5. Private Claims

I, Randy Kolehouse, in a field survey on July 25 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-11 Per G.L.O. notes, J. Wampler set a post in 1816 & 1817.

Table listing monuments: O.C.R.C., L.C.R.C. L. 7353 P. 577 1978, Kobs Survey 1978, Macomb County L.C.R.C. for A-11, NW 62.2' Nail 12" Elm, 1/2" Iron Bar, Nail & Washer in Tel. Pole N 39.52', L.C.R.C. L. 5778 P. 409 1993, SW 44.30' Nail 12" Elm, Nail & Washer in 24" Oak NE 33.58', Nail & Washer in Tel. Pole SE 61.35', 3/4" Iron Pipe, PK Nail in P. Pole SE 969.8', NE Cor. Sec. 36 Addison Twp., 1/2" Iron Bar South 14.76', Nail & Washer in Tel. Pole NW 24.68'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-11 Found 1/2" iron bar near C/L Brewer Road (gravel) running E-W 4' West of West edge Dequindre Road (asphalt) running N-Sly with 3/4" pipe (NW Cor., Sec. 31, T5N, R11E) 14.76' North. Checks the following witnesses.

Table listing witnesses: L.C.R.C. 7353 P. 577 1978, Kobs Survey 1978, Macomb County L.C.R.C. for A-11, N 39.30' Nail W Side Tel. Pole, N 39.30' Nail W Side Tel. Pole, L.C.R.C. L. 5778 P. 409 1993, NE Cor. Sec. 36 Addison Twp., 1/2" Iron Bar South 14.76'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11 Set a 5/8" rebar with brass cap stamped "Oakland County Remonumentation P.S. #25854" in place of found 1/2" iron bar.

- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NE Side of 15" Aspen S 50° E 51.32'
PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in W. Side MBT Pole N 39.30'
PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NW Side 8" Cherry S 70° W 63.76'
PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NE Side P. Pole S 35° E 82.22' PK 3/4" Iron Pipe N 14.76'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J Kolehouse Date 12/23/94
Surveyor's Michigan License No. 25854

