

**SURVEY & REMONUMENTATION**

LIBER **15234** PG **556**

FEB 295020003

MAY - 1 1995

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

\$ 7.00 MISCELLANEOUS RECORDING

2.00 REMONUMENTATION

PAID FEB 95 7:26 A.M. RECEIPT# 2B  
RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

**COMMISSION**

For corners in

For corners in	Located in:	Addison Township	Corner Code #
<u>Oakland</u> (County)			
1. Public Land Survey	T <u>5N</u> R <u>11E</u>		<u>M-12</u>
	T _____ R _____		_____
	T _____ R _____		_____
	T _____ R _____		_____
2. Property Controlling in Section	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____

**OK - T. SMITH**

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-12-94  
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on July 21 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

M-12 Per G.L.O. notes, J. Wampler set a post in 1816 and 1817.

Kay Engineering Survey 1992  
1/2" Iron with Cap  
N 45° E 48.2' to P.K. in 6" Tree  
S 30° E 81.00' to P.K. in 14" Tree  
S 45° W 49.6' to P.K. in 6" Cluster

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-12 Found iron with cap in C/L of Dequindre Road (gravel) running N-S. Checks the following witnesses.

Kay Engineering Survey 1992  
N 50° E 48.16' P.K. in SE Side 10" Hickory  
Checked Survey to Verify Corner

Brown Measures South 2652.30' to M-13

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-12 Set a 5/8" rebar with brass cap stamped "Oakland County Remonumentation P.S. #25854" in place of found rebar and cap.

PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in D.E. Pole ENE 57.63'  
PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NE Side 5" Pine N 35° W 52.75'  
PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in SE Side 10" Hickory N 50° E 48.16'  
PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in SE Side Tw. 12" Oak N 42° E 61.33'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse Date 12/23/94  
Surveyor's Michigan License No. 25854

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

