

SURVEY & REMONUMENTATION

LIBER 15234 PG 557

FEB 295020004

OK - T. SMITH

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland  
(County)

COMMISSION

Located in: Addison Township Corner Code #

- 1. Public Land Survey T 5N R 11E Corner Code # M-13  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

\$ 7.00 MISCELLANEOUS RECORDING  
\$ 2.00 REMONUMENTATION  
2 FEB 95 7:26 A.M. RECEIPT# 2B  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 12-12-94  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on July 25 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-13 Per G.L.O. notes, J. Wampler set a post in ?????.

O.C.R.C. 1975

- Nail & Washer in D.E. Pole NE 54.14'
- Nail & Washer in Wooden Sign Post ESE 56.03'
- Nail & Washer in D.E. Pole SE 59.35'

Record Survey L. 12114 P. 264 1991

- P.K. in 12" Cherry NNW 108.44'
- Chis. "X" on Large Rock NE 54.44'
- Nail & Tag #5390 in P. Pole SSE 59.28'
- Chis. "X" on Top S End of West 24" C.M.P. SW 41.65'

Brown Survey 1992

- 1/2" Iron
- N 45° E 54.6' Nail in P. Pole
- N 45° W 58.7' Nail in P. Pole
- S 45° E 59.2' Nail in P. Pole

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-13 Found P.K. in new bit. at C/L "X" of Dequindre Road (gravel) running N-S and 32 Mile Road (pavement) running E-W and checked following witnesses.

O.C.R.C. 1975

- P.K. & Tag in NW Side P. Pole N 30° E 54.61'
- Nail & Washer in NE Cor. Wood Sign Post S 37° E 56.01'

Record Survey L. 12114 P. 264 1991

- S 20° E 59.13' P.K. & Tag in SW Side D.E. Pole
- "X" Cut in Top S End C.M.P. West S 46° W 46.41'
- "X" Cut in Top of Large Rock N 41° E 54.43'

Brown Survey 1992

- N 33° W P.K. & Tag in NE Side
- D.E. Pole 58.76'

Upon returning to set monument, found a 5/8" iron bar with brass cap stamped Oakland County Remonumentation P.S. #22445 as set by Grant Ward.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-13 5/8" iron with brass cap stamped "Oakland County Remonumentation P.S. #22445" in a monument box.

- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #22445" in SW Side D.E. Pole S 20° E 59.13'
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #22445" in NE Side P. Pole N 33° W 58.76'
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #22445" in NW Side P. Pole N 30° E 54.61'
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #22445" in NE Cor. Wood Sign Post S 37° E 56.01'
- "X" Cut in Top S End C.M.P. West S 46° W 46.41'
- "X" Cut in Top of Large Rock N 41° E 54.43'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse Date 12/23/94

Surveyor's Michigan License No. 25854

