

STATE OF MICHIGAN
 COUNTY OF OCEANA
 RECEIVED FOR RECORD

3 DEC 1999 2:06:17 PM

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oceana (County)	Located In:	Corner Code #
1. Public Land Survey	T13N R15W	F-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

JOSEPH E. HERTEN
 REGISTER OF DEEDS

100927

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, J. Randolph Hepworth in a field survey on August 12 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-9 1/4 CORNER COMMON TO SECTIONS 21 & 28 T13N, R15W GREENWOOD TOWNSHIP
 GLO 36" Pine for quarter section post

LCRC # 100365, John Bueche #13027, 10/21/87, Set 1/2" rerod
 1/2 the distance and on line between the NW and NE corner of Sec 28 (2626.61')

- | | | | |
|--------------------------------------|--------------------------------------|--|--|
| C/L 2-track E-W 3'N | C/L 2-track N-S 34' W | | |
| 1) PK in E side 28" Oak N10°W 74.55' | 2) PK in S side 14" Oak S60°W 64.00' | | |
| 3) PK in W side 12" Oak S30°E 34.79' | 4) PK in E side 12" Oak S10°W 54.18' | | |

USFS Witness Card, John Bueche #13027, 1987, Set 1/2" rerod

See Witnesses for LCRC # 100365

Unrecorded Survey, JR Hepworth #26457, 10/5/89 Fd 1/2" Iron 40' E C/L N-S Rd; C/L E-W Rd

Oceana County Remonumentation
 Peer Group Reviewed & Approved

Date: 10-27-99

JRH
 J. Randolph Hepworth
 Oceana County Surveyor

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

I found a 1/2" Iron with no cap 3' south of the centerline of E-W Road and 40' east of centerline of N-S trail road as described by Bueche, 1987. All Bueche witnesses are standing and measure OK, except #2 is now a recent stump. Bueche apparently felt this corner to be lost and replaced it by single proportionate measurement.

I accept the 1/2" Iron as a careful and faithful re-establishment of the position of the original corner. No evidence is known to me that would lead me to believe the corner should be at another location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 4"x20" Harrison Cast Iron Monument, stamped "County Surveyor" and "26457" above the 1/2" Iron which was driven down.

60d spk	NW Face	8" Oak	258°az	63.74'	EDM
60d spk	E Face	32" Oak	339°az	74.37'	EDM
60d spk	NW Face	Power Pole	41°az	39.90'	EDM
60d spk	SW Face	14" W Oak	139°az	35.07'	EDM
60d spk	E Face	18" W Oak	184°az	54.10'	EDM



Signed by J. Randolph Hepworth
 Surveyor's Michigan License No. 26457

Date November 30, 1999