

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF OCEANA  
RECEIVED FOR RECORD

3 DEC 1999 2:07:17 PM

For corners in

Oceana

(County)

Located In:

Corner Code #

1. Public Land Survey

T	<u>13</u> N	R	<u>15</u> W	G-10
T	___	R	___	___
T	___	R	___	___
T	___	R	___	___
S	___	T	___	___
S	___	T	___	___
S	___	T	___	___
S	___	T	___	___

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

JOSEPH E. MERTEN  
REGISTER OF DEEDS

100931

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, J. Randolph Hepworth in a field survey on August 13, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	N
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-10 1/4 CORNER COMMON TO SECTIONS 27 & 28 T13N, R15W GREENWOOD TOWNSHIP

GLO J. Mullett 1838 SET POST 12" W. Oak N59°E (9lks) 5.9' 12" B. Oak S62°W (12lks) 7.9'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

I determined this corner to be non-existing. No history is available for this corner other than GLO. Corner falls in vicinity of a curve of N-S Road as it goes around the marsh. The only occupation found is the centerline of the N-S Road. An old overgrown road track continues northerly from the road curve along its centerline tangent.

I re-established this corner by single proportion from G-9 to G-11 and used the centerline of the old road track for the easting position.

I accept the corner so established as a careful and faithful re-establishment of the position of the original corner. No evidence is known to me that would lead me to believe the corner should be at another location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 4"x20" Harrison Cast Iron Monument, stamped "County Surveyor" and "26457"					
60d spk	NE Face	6" W. Oak	328°az	20.38'	EDM
60d spk	SW Face	Power Pole	319°az	126.62'	EDM
60d spk	N Face	24" tw Oak	283°az	77.51'	EDM
60d spk	E Face	Power Pole	171°az	134.13'	EDM
60d spk	N Face	8" tr. Cherry	95°az	87.77'	EDM

Oceana County Remonumentation  
Peer Group Reviewed & Approved

Date: 10-27-99

JRH  
J. Randolph Hepworth  
Oceana County Surveyor



Signed by J. Randolph Hepworth  
Surveyor's Michigan License No. 26457

Date November 30, 1999