

STATE OF MICHIGAN
 COUNTY OF OCEANA
 RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

3 DEC 1999 2:07:47 PM

For corners in

Oceana
 (County)

Located in: Corner Code #

- | | | |
|------------------------------------|----------------------------|-------------|
| 1. Public Land Survey | T <u>13</u> NR <u>15</u> W | <u>G-12</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

JOSEPH E. HERTEN
 REGISTER OF DEEDS

100933

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, J. Randolph Hepworth, in a field survey on August 12, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-12 1/4 CORNER COMMON TO SECTIONS 33 & 34 T13N, R15W GREENWOOD TOWNSHIP

GLO J. Mullett 1838 SET POST 10" Maple N88°E (17lks) 11.2' 10" Maple S87°W (23lks) 15.2'

Book A, Pg. 124, S Edson, 1881; "Sand Stone with a notch on top."
 Book A, Pg. 166, S Edson, 1881; "Sand Stone with a notch on top."

OCRC WITNESS BOOK Undated Large Stone
 30" (word is missing) West 31.4'
 10" Silver Maple S35°W 58.0'
 30" Tr. Elm S60°E 47.6'

Unrecorded Survey, JR Hepworth #26457, 10/27/95 Fd 1/2" Iron / cap # 18987
 Fd 16d Spk In N Face 14" Maple 96°Az 40.61'
 16d Spk in SE Face P.Pole 45°Az 90.93'
 16d Spk in E Face 24" Maple 204°Az 66.88'
 16d Spk in N Face 50" Oak 270°Az 67.78'

Recorded Survey Jkt # 593, Carl Englert, Jr., # 18987, 8/21/96, Set Iron Bar (7/12/95)

Oceana County Remonumentation
 Peer Group Reviewed & Approved

Date: 10-27-99

JRH
 J. Randolph Hepworth
 Oceana County Surveyor

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

I found a 1/2" Iron and cap (#18987) in the centerline of N-S Road. Occupation lines run to the east and to the west. All OCRC witnesses are gone. No documentation is known to me as the method of how Englert set this corner other than the local collateral evidence as to the position of the original corner.

I accept the Iron as the best available evidence of the position of the original corner. No evidence is known to me that would lead me to believe the corner should be at another location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 4"x20" Harrison Cast Iron Monument, stamped "County Surveyor" and "26457" above the 1/2" Iron which was driven down.

60d spk	SE Face	Power Pole	42°az	90.87'	EDM
60d spk	N Face	30" Maple	227°az	45.72'	EDM
60d spk	N Face	12" Ash	283°az	29.58'	EDM
60d spk	NE Face	Power Pole	160°az	230.93'	EDM
60d spk	E Face	24" Maple	204°az	66.88'	EDM

Signed by J. Randolph Hepworth
 Surveyor's Michigan License No. 26457

Date November 30, 1999

