

FEB 2 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

100636

95 JUL 10 P2:48

For corners in

Oceana

(County)

Located In:

Corner Code #

1. Public Land Survey	T	13N	R	15W	I-8
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		
	S		T		
3. Miscellaneous Property in Sec.	S		T		
	S		T		

Joseph E. Martin
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

J. Randolph Hepworth

June 14, 1995

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-8 1/4 Corner Common to Sections 22 and 23 T13N, R15W GREENWOOD TOWNSHIP

GLO Set Post 10" W Oak N12°W 17.2 22" Pine S70°E 16.5

HC Salisbury, 1913; FB#6; Oak Stake 4" Oak N80°W 31' 14" Pine Stump S43°W 51'

LCRC 100246; James Evans, PS22431; 6-15-79 Set 1/2" pipe from OCRC witness- (new road construction)
10" Tw B Oak S80°E 40.34 18" B Oak S45°W 51.54 18" B Oak S70°W 44.42 10" B Oak N30°W 64.38

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner

I found a 1/2" Pipe near the surface and in the centerline of a north-south asphalt road. No occupation is visible east or west. Found Pipe fits LCRC 100246 witnesses.

Further search of the area failed to yield any other evidence for a conflicting position for the corner. This represents the best available evidence for the position of the corner. The Found 1/2" Pipe is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

I-8 1/4 Corner Common to Sections 22 and 23 T13N, R15W GREENWOOD TOWNSHIP

Set 4"x20" Harrison County Surveyor Monument above the found 1/2" Pipe

60d spk	S Face	16" B Oak	264°az	44.40	EDM
60d spk	SE Face	18" B Oak	224°az	51.53	EDM
60d spk	S Face	10" Tw B Oak	104°az	40.31	EDM
60d spk	SW Face	18" B Oak	141°az	54.12	EDM
60d spk	SE Face	6" W Pine	33°az	76.15	EDM



Oceana County Remonumentation
Peer Group Reviewed & Approved

Date: 5-25-95

JRH
J. Randolph Hepworth
Oceana County Surveyor

Signed by *J. Randolph Hepworth*
Surveyor's Michigan License No. 26457

Date July 6, 1995