

FEB 22 1995  
COMMISSIONER

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

100641  
95 JUL 10 P2:49

For corners in Oceana County  
(County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

|                                    |                         |             |
|------------------------------------|-------------------------|-------------|
| 1. Public Land Survey              | T <u>13</u> R <u>15</u> | <u>J-11</u> |
|                                    | T _____ R _____         | _____       |
|                                    | T _____ R _____         | _____       |
|                                    | T _____ R _____         | _____       |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____       |
|                                    | S _____ T _____ R _____ | _____       |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____ | _____       |
|                                    | S _____ T _____ R _____ | _____       |

*Joseph E. Meitner*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

|    |    |    |    |    |    |    |   |   |   |   |   |   |   |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

I, J. Randolph Hepworth, in a field survey on June 12, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

**J-11 1/4 Corner Common to Sections 26 and 35 T13N, R15W GREENWOOD TOWNSHIP**

GLO Set Post 10" Beech N10°E 25.1 14" Beech N85°W 15.2

Book A, Pg 136; S Edson, 1881; A Bluish Stone, 20"x14"x10", two seams nearly at right angles. From said Stone is another 16"x8"x4" N18°W 28.7'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner

No monument was found at this location. Corner was re-established by single proportion (equi-distant) between I-11 to K-11 and on a straight line. Corner falls in the center of an east-west asphalt road and on old tree lines north-south. Distance measurement to I-11 & K-11 compare favorably with Edson, 1881.

Further search of the area failed to yield any other evidence for a conflicting position for the corner. This represents the best available evidence for the position of the corner. The Re-established position is accepted as a careful and faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

**J-11 1/4 Corner Common to Sections 26 and 35 T13N, R15W GREENWOOD TOWNSHIP**

|                                              |              |        |         |     |  |
|----------------------------------------------|--------------|--------|---------|-----|--|
| Set 4"x20" Harrison County Surveyor Monument |              |        |         |     |  |
| 60d spk E Face                               | Power Pole   | 177°az | 63.37   | EDM |  |
| 60d spk NW Face                              | 8" Poplar    | 236°az | 46.38   | EDM |  |
|                                              | top center   | 295°az | 80.2    | EDM |  |
| 60d spk NE Face                              | 6" tw Poplar | 298°az | 60.92   | EDM |  |
| 60d spk W Face                               | 8" Poplar    | 19°az  | 26.33   | EDM |  |
|                                              | I-11 corner  | west   | 2645.00 | EDM |  |
|                                              | K-11 corner  | east   | 2645.00 | EDM |  |

Oceana County Remonumentation  
Peer Group Reviewed & Approved  
Date: 6-25-95  
JRH  
J. Randolph Hepworth  
Oceana County Surveyor

Signed by J. Randolph Hepworth  
Surveyor's Michigan License No. 26457

Date 6-10-95

