

RF

100912

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF OCEANA
RECEIVED FOR RECORD

3 DEC 1999 2:02:27 PM

JOSEPH E. MERTEN
REGISTER OF DEEDS

For corners in
Oceana
(County)

Located In: Corner Code #

1. Public Land Survey T13N R16W F-1
T R
T R
T R

2. Property Controlling S T R
in Section S T R

3. Miscellaneous S T R
Property in Sec. S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

J. Randolph Hepworth Aug. 31, 1999
in a field survey on 19 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

F-1 N 1/4 CORNER OF SECTION 4 T13N, R16W OTTO TOWNSHIP

GLO NO POST SET by Government Surveyors

Book A, Pg. 286; H.A. Grant, 1891, Sec. 4, T13N, R16W; "Set cedar stake."
Book A, Pg. 288; H.A. Grant, 1891; Section 33, T14N, R16W

OCRC Witness Book 1961 Wood Stake
6" Cedar S45°E 26.7' Light Pole N45°E 61.5'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

I found a 3/4" T Iron with no cap at surface of the road 27.11' west of the F-13 corner. Corner falls 9'South and 27' West of centerline of Road intersection E-W-N. No occupation to south is visible in the swamp. All OCRC witnesses are gone. From previous measurements to this corner, I know this iron to be midway between E-1 and G-1 corners and is on line with F-13 of T14N and E-13 of T14N.

I accept the T Iron as the best available evidence of the position of the original corner. No evidence is known to me that would lead me to believe the corner should be at another location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


Set 4"x20" Harrison Cast Iron Monument, stamped "County Surveyor" and "26457" above the T Iron which was driven down.

F-13 T14N corner	Harrison Monument	west	27.16'	EDM
60d spk SW Face	16" Cedar	162°az	22.35'	EDM
60d spk N Face	Guy Pole	104°az	69.40'	EDM
60d spk SE Face	Power Pole	52°az	82.56'	EDM
60d spk SW Face	Power Pole	320°az	65.42'	EDM

Oceana County Remonumentation
Peer Group Reviewed & Approved

Date: 10-27-99

J. Randolph Hepworth
Oceana County Surveyor



igned by J. Randolph Hepworth
urveyor's Michigan License No. 26457

Date December 1, 1999