

FEB 2 2 1995

STATE OF MICHIGAN
COUNTY OF OCEANA
RECEIVED FOR RECORD

10063

COMMISSIONER LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

95 JUL 10 P2:48

For corners in

Oceana County
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 13 R 18 I-8
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

Joseph E. Martin
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, J. Randolph Hepworth, in a field survey on June 12, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
I-8 1/4 Corner Common to Sections 22 and 23 T13N, R18W CLAYBANKS TOWNSHIP

- GLO SET POST 12" Beech S51°W 21.1' 10" Hemlock N59°E 7.9'
- Book A, Pg 138; S. Edson, 1883; "A piece of lightning rod 5ft. long, over which is placed a gray stone 15" long and 10" by 7"
- Book A, Pg 140; S. Edson, 1882; "A piece of lightning rod 5ft. long over which is placed a brownish stone about 15" long and 7" wide"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner

I found a 1" Iron at the surface and center of a north-south asphalt road. Center of a gravel road runs west and an old fence (lying down) runs to the east. Upon excavation and removal of the 1"x18" Iron, no other iron objects were detected. Original topsoil grade is at 18" below surface.
Further search of the area failed to yield any other evidence for a conflicting position for the corner. This represents the best available evidence for the position of the corner. The Found 1" Iron is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

- I-8 1/4 Corner Common to Sections 22 and 23 T13N, R18W CLAYBANKS TOWNSHIP
- Set "COUNTY SURVEYOR" HARRISON 4"x20" cast iron Monument above the found 1" Iron which was driven down.
- 60d spk N Face Power Pole 264°az 260.55 EDM
- 60d spk NE Face 8" R Oak 322°az 69.61 EDM
- 60d spk E Face Power Pole 98°az 34.69 EDM
- 60d spk SW Face 14" Basswood 166°az 98.61 EDM

Oceana County Remonumentation
Peer Group Reviewed & Approved
Date: 5-25-95
JRH
J. Randolph Hepworth
Oceana County Surveyor

Signed by *J. Randolph Hepworth* Date 6-12-95
Surveyor's Michigan License No. 26457

