

FEB 2 1996

STATE OF MICHIGAN  
COUNTY OF OCEANA  
RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

100662

'95 DEC 15 P 3:02

For corners in  
Oceana  
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 14N R 15W F-9
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Section S T R
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

*Jeff E. Metten*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, J. Randolph Hepworth, in a field survey on Nov. 20, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

**F-9 1/4 CORNER COMMON TO SEC. 21 AND 28 T14N, R15W NEWFIELD TOWNSHIP**

GLO SET POST 12" Maple N70°E 9.9' 8" Hemlock S51°E 5.3'  
Book A, Pg 578, H.C. Hawley, 1883, "Hole 3' deep, 3 1/4" dia. filled with charcoal, broken bricks, crockery, etc.  
12" Maple N70°E 9.9' 10" Hemlock N35°W 11.9'  
Book C, Pg 2; F. Wetmore, 1900; Old quarter post.  
Book B, Pg 8; F. Wetmore, 1900; "Old quarter post set by Hawley."

N. Ochs Ps 22439 Unrecorded Survey May 1976 Set 1/2" Pipe by projection and measurement west from a found Wagon Hub & crockery at the E 1/16 Cor and SE Corner of Section 21. Measurement = 1313.98'. No Witnesses given to me.

LCRC #100483 R Hepworth PS26457 12-4-92 Found 1/2" Pipe, Grader blade beside-guard stake  
Tw 8" 6" Maple S 15.46' 10" Cedar NE 16.19' 16" W Pine NW 37.40' 18" Hemlock SE 43.22'  
10' W. Pine N 40.12'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner

I found a 1/2" Pipe projecting 6" above the ground 8" SW of a grader blade projecting 3 feet. Pipe is 5 feet north of the center of an old east-west road bed at the edge of swampy area. On excavation and removal of the pipe, I did not find any evidence of brick, crockery or charcoal. Corner falls in 2 foot ± fill area of the road bed in the swamp. No occupation is visible to the north; a single-strand wire tree-to-tree runs to the south from this corner.

Further search of the area failed to yield any other evidence for a conflicting position for the corner. This represents the best available evidence for the position of the corner. The found 1/2" Pipe is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

**F-9 1/4 CORNER COMMON TO SECTIONS 21 AND 28 T14N, R15W NEWFIELD TOWNSHIP**

Set "County Surveyor" Harrison 4"X20" Cast Iron Monument in place of the found 1/2" Pipe

60d spk W Face	10" Pine	N10°E	40.12	EDM
60d spk S Face	12" Cedar	N80°E	16.19	EDM
60d spk E Face	18" Hemlock	S15°E	43.22	EDM
60d spk NE Face	16" W Pine	N45°W	37.40	EDM
60d spk W Face	8",6" Maple	S5°W	15.46	EDM

Original Monumentation  
Peer Group Reviewed & Approved

Date: 12-7-95

JRH  
J. Randolph Hepworth  
Oceana County Surveyor



Signed by J. Randolph Hepworth  
Surveyor's Michigan License No. 26457

Date 12-14-95