

MAY 18 1987

STATE OF MICHIGAN
COUNTY OF OCEANA
RECEIVED FOR RECORDING

LAND CORNER RECORDATION CERTIFICATE

100691

Filing Requirement of Act 74, Mich. P.A. 1970 '96 DEC 19 AM 12

For corners in Oceana (County) Located In: Corner Code #

- 1. Public Land Survey T 14N R 15W I-4
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Section S _____ T _____ R _____

Joseph E. Martins
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, J. Randolph Hepworth, in a field survey on July 12, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-4 1/4 CORNER COMMON TO SECTIONS 10 & 11 T14N, R15W, NEWFIELD TWP

GLO SET POST 18" Beech S60°E 25.7' 15" Beech N53°W 23.8'

BOOK A, PG 576 ; Henry C. Hawley, 1885; Hole 3' deep & 3 1/4" dia filled w/ brick, charcoal, & crockery
Beech W 71.9' 30" Sym (?) S59°W 53.5'

BOOK C, PG 44; unsigned, circa 1903; Fd remains of 1882 Hawley corner. Set Iron Pipe (Illegible) by 1 1/4" with crockery. NO WITNESSES.

OCRC, undated pre-1950; Corner not described: Geo. Survey Post S30°W 45.5 14" Elm N70°W 60.0

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner

I found a 3/4" Iron in the center of the surface of a north-south & east asphalt road and center of a dirt road to the west. Upon removal of the 3/4" Iron, I found it to be above a 1" Iron about 18" below the surface. OCRC witness to the USGS Benchmark monument measures good.

The 3/4" Iron above the 1" Iron IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

I-4 1/4 CORNER COMMON TO SECTIONS 10 & 11 T14N, R15W, NEWFIELD TWP

Set 5/8"x32" Iron with cast aluminum cap stamped "Oceana County Remonumentation" and "26457" in place of found 3/4" Iron and above the 1" Iron

60d spk NE Face	Power Pole	313°az	99.97	EDM
60d spk N face	16" Maple	250°az	77.45	EDM
20d spk NW Face	16" Maple	208°az	55.92	EDM
60d spk NW Face	Power Pole	36°az	78.51	EDM
USGeological Survey Benchmark "TT23 Tex 1930 B36"		211°az	45.42	EDM

Oceana County Remonumentation
Peer Group Reviewed & Approved

Date: 8-18-94

JRH
J. Randolph Hepworth
Oceana County Surveyor



Signed by J. Randolph Hepworth Date December 5, 1996

Surveyor's Michigan License No. 26457