

**SURVEY &
REMONUMENTATION**

JAN 11 1999

STATE OF MICHIGAN
COUNTY OF OCEANA
RECEIVED FOR RECORD

28 DEC 1998 4:37:03 PM

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oceana

(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|-------------|---|-------------|------------|
| 1. Public Land Survey | T | <u>14</u> N | R | <u>17</u> W | <u>I-8</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

JOSEPH E. NERTEN
REGISTER OF DEEDS

100886

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

J. Randolph Hepworth November 10, 98
I, _____, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-8 1/4 CORNER COMMON TO SECTIONS 22 & 23 T14N, R17W SHELBY TOWNSHIP

GLO Set post 8"Lynn S76°E 13.2' 15"Beech S74°W 15.2'
No other historical documentation is known to me.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

I found at the intersection of old woven-wire fence lines N-S and E-W (lying down) a red granite stone. This Stone is nicely dressed with flat sides standing vertical - 4"x5" at the top, pyramidal shaped to 7"x10" at the base and 20" long. Stone was found to be braced with small stones at the base.

This represents the best available evidence for the position of the corner. The found stone is accepted as a careful and faithful perpetuation of the position of the original corner. No evidence is known to me that would lead me to believe that the corner should be at another location. I placed a 4"x20" Harrison Cast Iron Monument stamped "County Surveyor" and "26457" at the position found and laid the stone back in the excavated hole on the north side of the monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

I-9 CORNER COMMON TO SECTIONS 22, 23, 26, & 27 T14N, R17W SHELBY TOWNSHIP

"County Surveyor" Harrison 4"x20" Cast Iron Monument

60d spk	W Face	16" Maple	155°az	5.47'	EDM
60d spk	N Face	4" Beech	83°az	50.24	EDM
60d spk	NW Face	10" Cherry	213°az	42.51	EDM
60d spk	SW Face	12" Cherry	297°az	48.50	EDM

Oceana County Remonumentation
Peer Group Reviewed & Approved

Date: 12-10-98

JRH
J. Randolph Hepworth
Oceana County Surveyor

Oceana County Remonumentation
Peer Group Reviewed & Approved

Date: 12-10-98

JRH
J. Randolph Hepworth
Oceana County Surveyor



Signed by J. Randolph Hepworth
Surveyor's Michigan License No. 26457

Date 12-21-98