

**SURVEY & REMONUMENTATION**

FEB 02 1998

100809

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oceana  
(County)

Located in:

Corner Code #

- |                                    |   |     |   |     |      |
|------------------------------------|---|-----|---|-----|------|
| 1. Public Land Survey              | T | 14N | R | 17W | I-10 |
|                                    | T |     | R |     |      |
|                                    | T |     | R |     |      |
|                                    | T |     | R |     |      |
| 2. Property Controlling in Section | S |     | T |     | R    |
|                                    | S |     | T |     | R    |
| 3. Miscellaneous Property in Sec.  | S |     | T |     | R    |
|                                    | S |     | T |     | R    |

STATE OF MICHIGAN  
COUNTY OF OCEANA  
RECEIVED FOR RECORD

14 Jan 1998 9:33:41 AM

JOSEPH E. MERTEN  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

J. Randolph Hepworth  
I, \_\_\_\_\_, in a field survey on June 27, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

I-10 1/4 CORNER COMMON TO SECTIONS 26 & 27 T14N, R17W SHELBY TOWNSHIP

GLO Set post 8" Beech N38°E 3.9' 12" Beech S25°W 29.7'  
Book A, Pg 280; H, Grant, 1891; Corner not described or witnessed.

LCRC # 100295, JR Hepworth, # 26457, 1/19/82, Set 1/2" Iron  
Fence to W Center N-S Grade  
10" Oak SSE 29.80' 3" Oak W 26.64'  
12" Tw Beech NW 29.30'

Oceana County Remonumentation  
Peer Group Reviewed & Approved  
Date: 10-16-97  
JRH  
J. Randolph Hepworth  
Oceana County Surveyor

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

I found the JRH 1/2" Iron as described in LCRC 100295. A search of the vicinity failed to uncover any other monumentation. An old fence runs to the West and remnants of an old fence runs to the East. Corner falls in approximate centerline of old grade and is 16' West of present-day N-S 2-track road.

This represents the best available evidence for the position of the corner. The found JRH 1/2" Iron is accepted as a careful and faithful perpetuation of the position of the original corner. No evidence is known to me that would lead me to believe that the corner should be at another location. I placed a 4"x20" Harrison Cast Iron Monument stamped "County Surveyor" and "26457" at the position found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

I-10 1/4 CORNER COMMON TO SECTIONS 26 & 27 T14N, R17W SHELBY TOWNSHIP  
"County Surveyor" Harrison 4"x20" Cast Iron Monument

60d spk	centerline of N-S two-track	East	16'
60d spk	SE Face	46°az	10.76
60d spk	SW Face	304°az	29.24
60d spk	E Face	220°az	36.21
60d spk	W Face	162°az	29.68
	6" Oak		
	14" tw Beech		
	clip 12" Beech		
	14" Oak		



Signed by J. Randolph Hepworth  
Surveyor's Michigan License No. 26457

Date November 29, 1997