

**SURVEY & REMONUMENTATION**

FEB 02 1998

100811

SECTION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Oceana

(County)

Located In:

Corner Code #

1. Public Land Survey	T	14N	R	17W	J-9
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

STATE OF MICHIGAN  
COUNTY OF OCEANA  
RECEIVED FOR RECORD

14 Jan 1998 9:34:08 AM

JOSEPH E. MERTEN  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, J. Randolph Hepworth, in a field survey on July 11, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

**J-9 1/4 CORNER COMMON TO SECTIONS 23 & 26 T14N, R17W SHELBY TOWNSHIP**

GLO Set post 10" Beech N19°W 6.6' 8" Beech S43°E 20.5'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

I found a 1/2" Iron and cap, "HEI 14091", in the centerline of an E-W 2-track trail. Old Fence remnants and plow row run to the N and to the S from this corner. No record documentation is known to me regarding this corner other than GLO of which no evidence was found.

This represents the best available evidence for the position of the corner. The found 1/2" Iron & Cap is accepted as a careful and faithful perpetuation of the position of the original corner. No evidence is known to me that would lead me to believe that the corner should be at another location. I placed a 4"x20" Harrison Cast Iron Monument stamped "County Surveyor" and "26457" at the position found above the Iron which was driven down.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

**J-9 1/4 CORNER COMMON TO SECTIONS 23 & 26 T14N, R17W SHELBY TOWNSHIP**

Set "County Surveyor" Harrison 4"x20" Cast Iron Monument					
60d spk	E Face	40" W Pine	188°az	12.59	EDM
60d spk	NW Face	12" R Oak	207°az	25.06	EDM
60d spk	SW Face	8" R Oak	317°az	19.31	EDM
60d spk	E Face	24" W Oak	26°az	25.52	EDM
60d spk	SE Face	32" W Oak	68°az	41.15	EDM
60d spk	S Face	10" W Pine	98°az	66.60	EDM

Oceana County Remonumentation  
Peer Group Reviewed & Approved

Date: 10-16-97  
JRH

J. Randolph Hepworth  
Oceana County Surveyor



Signed by J. Randolph Hepworth  
Surveyor's Michigan License No. 26457

Date November 29, 1997