

SURVEY & REMONUMENTATION

OCT 27 1993

COMMISSION

**OCEANA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
COUNTY OF OCEANA
RECEIVED FOR RECORD

100496

'93 OCT -7 P2:44

For corners in
OCEANA

(County)

Located In:

Corner Code =#

1. Public Land Survey	T	14N	R	18W	I-12
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Joseph E. Martin
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

J. Randolph Hepworth September 30, 1993

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-12 1/4 CORNER COMMON TO SECTIONS 34 and 35 BEHONA TWP; T14N, R18W
GLO SET POST 15" BEECH N89°E 30.4' 18" BEECH N80°W 25.1'
BOOK A-274 GRANT, 1891 ED STONE PREVIOUSLY SET
BOOK A-276 GRANT, 1891 SAME

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner

FOUND 9X8X15 STONE WITH SMALL POINT UP, 2 FEET BELOW ROAD SURFACE; RAISED WITH 1/2"X2" IRON FOR TEMPORARY MONUMENT; AN IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

I-12 1/4 CORNER COMMON TO SECTION 34 & 35, T14N, R18W
SET "COUNTY SURVEYORS" HARRISON 4"X20" CAST IRON MONUMENT ON TOP OF FOUND STONE.

CENTER OF T-ROAD INTERSECTION E-W & S; OLD FENCE TO NORTH				
60d SPK SW FACE	POWER POLE	S16°E	222.38'	EDM
60d SPK NE FACE	POWER POLE	S55°E	75.64'	EDM
60d SPK SE FACE	8" TW CHERRY	N45°E	36.44'	TAPED
W EDGE BURIED CABLE SIGN		N09°W	16.42'	TAPED
CENTER	TEL. JUNC. BOX	N59°W	32.6'	TAPED



Signed by *J. Randolph Hepworth* Date October 6, 1993
Surveyor's Michigan License No. 26457