

SURVEY & REMONUMENTATION

OCT 27 1993

COMMISSION

**OCEANA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
COUNTY OF OCEANA
RECEIVED FOR RECORD

100503

'93 OCT -7 P2:45

For corners in

<u>OCEANA</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>18W</u>	<u>I-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____	Recorded Plat _____	
5. Private Claims _____		

Joseph E. Mertens
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, J. Randolph Hepworth, in a field survey on September 30, 1993

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

I-13 CORNER COMMON TO SECTIONS 34 and 35; BENONA TWP; T14N, R18W
 GLO SET POST 24" BEECH N36°W 28.4' 18" BEECH N74°E 28.4'
 BOOK A-224 HYDE, 1889 SET STONE AT GLO POSITION
 BOOK A-274 GRANT, 1891 STONE PREVIOUSLY SET AT GLO CORNER
 BOOK A-276 GRANT, 1891 SAME
 QCRC WITNESS: PLOW POINT 20" MAPLE S45°W 38.0; TEL POLE S25°E 51.8'
 LCRC #100243 J CAMPBELL, PS 15397 FOUND PLOW POINT RAISED W/ 1/2" IRON
 P POLE S60E 67.2
 TEL BOX N60E 53.8
 STOP SIGN N30W 58.8

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner

FOUND 1/2" IRON AT + ROAD INTERSECTION E-W & N-S AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

I-13 CORNER COMMON TO SECTIONS 34 & 35, T14N, R18W
 SET "COUNTY SURVEYOR" HARRISON 4"X20" CAST IRON MONUMENT IN PLACE OF FOUND 1/2" IRON on top of plow point

16d SPK E FACE	POWER POLE	S30°W	63.81'	TAPED
16d SPK E FACE	POWER POLE	S30°E	74.28'	TAPED
60d SPK W FACE	8" MAPLE	N30°E	52.38'	TAPED
CENTER	STOP SIGN	N20°W	54.5'	TAPED



Signed by *J. Randolph Hepworth*
 Surveyor's Michigan License No. 26457

Date October 6, 1993