

**SURVEY & REMONUMENTATION**

OCT 27 1993

COMMISSION

**OCEANA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
COUNTY OF OCEANA  
RECEIVED FOR RECORD  
**100500**  
'93 OCT -7 P2:44

For corners in  
OCEANA  
(County)

Located In: Corner Code #

- |                                    |   |     |   |     |      |
|------------------------------------|---|-----|---|-----|------|
| 1. Public Land Survey              | T | 14N | R | 18W | J-11 |
|                                    | T |     | R |     |      |
|                                    | T |     | R |     |      |
|                                    | T |     | R |     |      |
| 2. Property Controlling in Section | S |     | T | R   |      |
|                                    | S |     | T | R   |      |
| 3. Miscellaneous Property in Sec.  | S |     | T | R   |      |
|                                    | S |     | T | R   |      |

*Joseph E. Martin*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

J. Randolph Hepworth September 30, 1993

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

J-11 1/4 CORNER COMMON TO SECTIONS 26 AND 35 BENONA TWP; T14N, R18W  
GLO SET POST 12" HEMLOCK N04°W 6.6' 10" HEMLOCK S36°E 10.6'  
BOOK A-276 GRANT, 1891 CEDAR POST AT GLO CORNER

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner**

FOUND REMAINS OF ANCIENT FENCE POST AT FENCE INTERSECTION E-W & S; DISTANCE TO EAST FITS GRANT MEASUREMENTS TO OCCUPATION LINE (670.2' MEASURED) - GRANT 669.9' RECORDED TO ANCIENT FENCE LINE. AND TO NORTHEAST CORNER OF SEC. 35- 2680.65' MEASURED; 2679.6' GRANT RECORD. SET TEMPORARY 1/2" X 2" IRON IN POST REMAINS AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.**

J-11 1/4 CORNER COMMON TO SECTIONS 26 AND 35, T14N, R18W  
SET "COUNTY SURVEYOR" HARRISON 4" X 2" CAST IRON MONUMENT IN PLACE OF SET 1/2" IRON AT OLD POST

60d SPK S FACE	48" CHERRY	EAST	66.91'	TAPED
60d SPK NW FACE	16" HEMLOCK	N65°E	50.79'	TAPED
60d SPK NW FACE	24" BEECH	N45°E	39.81'	TAPED
60d SPK SE FACE	16" HEMLOCK	N15°E	12.46'	TAPED
60d SPK N FACE	8" HEMLOCK	S80°W	25.70'	TAPED

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



Signed by *J. Randolph Hepworth*  
Surveyor's Michigan License No. 26457

Date October 6, 1993