

**SURVEY & REMONUMENTATION**

OCT 27 1993

COMMISSION

OCEANA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF OCEANA  
RECEIVED FOR RECORD

100502

'93 OCT -7 P2:45

For corners in  
OCEANA

(County)

Located In:

Corner Code #

- |                                    |                         |       |
|------------------------------------|-------------------------|-------|
| 1. Public Land Survey              | T 14N R 18W             | J-13  |
|                                    | T _____ R _____         | _____ |
|                                    | T _____ R _____         | _____ |
|                                    | T _____ R _____         | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
|                                    | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____ | _____ |
|                                    | S _____ T _____ R _____ | _____ |

*Joseph E. Martin*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, J. Randolph Hepworth, in a field survey on September 30, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-13 1/4 CORNER SECTION 35 BENONA TWP; T14N, R18W  
GLO SET POST 6" BEECH N45°W 26.4' 5" BEECH N40°E 21.8'  
BOOK A-3 EDSON, 1880 SET REDDISH STONE 3x10x13 POINT UP WITH CHISKLED 'X' AT GLO CORNER  
BOOK A-276 GRANT, 1891 STONE PREVIOUSLY SET AT GLO CORNER  
BOOK A-224 HYDE, 1889 RED STONE PREVIOUSLY SET (IMPLIED TO BE COMMON WITH T13N & T14N  
OCRC WITNESS: 1" IRON  
T POLE N45°W 39.8 SE COR CULVERT HEADWALL 14.3 8" W BIRCH N30°E 49.0  
LCRC #100127 J NORDLUND, PS 16345 SET PK NAIL FROM OCRC WITNESS  
J-1 N 1/4 COR, SEC 2, T13N, R18W  
GUY POLE NW 47.4 18" ASH NE 61.0 P POLE SW 54.5  
LCRC #100269 R HEPWORTH, PS 26457 SET 1/2" IRON FROM NORDLUND SURVEY  
J-1 N 1/4 COR, SEC 2, T13N, R18W  
RD NAME SIGN N 16.5 PP SW 57.83  
NW COR SCHOOL HSE SE 170.15 16" ASH SW 103.77

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner

RE-ESTABLISHED CORNER BY PRORATING BETWEEN SW & SE CORNERS OF SECTION 35, USING HA GRANT, 1891 SURVEY MEASUREMENTS AND B HOLDING FOR LINE CORNER ACCEPTED AS N 1/4 CORNER OF SEC 2, T13N, R18W WHICH IS 13.64' EAST. AND IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

J-13 SOUTH 1/4 CORNER, SECTION 35, T14N, R18W BENONA TOWNSHIP  
SET "COUNTY SURVEYOR" HARRISON 4"x20" CAST IRON MONUMENT IN PLACE OF SET 1/2" IRON.

FOUND 1/2" IRON	T13N, R18W CORNER	EAST	13.64'	TAPED
W EDGE	STOP SIGN	S35°E	53.03'	TAPED
60d SPK SE FACE	POWER POLE	E25°W	49.59'	TAPED
60d SPK E FACE	16" ASH	S10°W	101.23'	TAPED
16d SPK SW FACE	GUY POLE	N25°W	40.59'	TAPED



Signed by J. Randolph Hepworth  
Surveyor's Michigan License No. 26457

Date October 6, 1993

C.93