

SURVEY & REMONUMENTATION

OCT 27 1993

**COMMISSION OCEANA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
COUNTY OF OCEANA
RECEIVED FOR RECORD
100499
'93 OCT -7 P2:44

For corners in
OCEANA

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>18W</u>	<u>K-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Joseph E. Mertens
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, J. Randolph Hepworth, in a field survey on September 30, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-12 1/4 CORNER COMMON TO SECTIONS 35 AND 36 BENONA TWP; T14N, R18W
GLO SET POST 12" SUGAR S47°E 15.5' 8" BEECH N44°W 24.4'
OCRC WITNESS: 3/4" GAS PIPE
REA P POLE S45°W 52.9' TEL POLE EAST 38.0'
BOOK A-66 EDSON, 1880 CORNER NOT DESCRIBED
BOOK A-276 GRANT, 1891 BLUISH STONE 5X8X11

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner

ESTABLISHED FROM HA GRANT SURVEY OF 1891; PRORATED DISTANCE FROM NE COR TO SE CORNER OF SECTION 35 AND USING GRANT DISTANCE FROM OCCUPATION WEST ON E-W 1/4 LINE. AND IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

K-12 1/4 CORNER COMMON TO SECTIONS 35 AND 36
SET "COUNTY SURVEYOR" HARRISON 4"X20" CAST IRON MONUMENT AT RE-ESTABLISHED POSITION
C/L N - S ROAD @ SOUTH BANK OF DITCH TO EAST
60d SPK NE FACE POWER POLE N09°W 204.64' EDM
60d SPK NE FACE GUY POLE S37°E 55.20' TAPED
S EDGE STOP SIGN N67°W 43.61' TAPED
60d SPK SE FACE POWER POLE S34°W 53.97' TAPED
60d SPK SE FACE POWER POLE/TRANSF S05°W 268.98' EDM



Signed by *J. Randolph Hepworth*
Surveyor's Michigan License No. 26457

Date October 6, 1993

11-5-93