

**SURVEY & REMONUMENTATION**

OCT 27 1993

**COMMISSION**

**OCEANA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
COUNTY OF OCEANA  
RECEIVED FOR RECORD  
**100501**  
'93 OCT -7 P2:44

For corners in

<u>OCEANA</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>14N</u> R <u>18W</u>	<u>M-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*Joseph E. Melius*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, J. Randolph Hepworth, in a field survey on September 30, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

M-13 SE CORNER SEC. 36 T14N, R18W BENONA TWP; T14N, R18W  
GLO SET POST 10" BEECH N57°W 7.9' 8" SUGAR S75°E 8.6'  
BOOK A-66 EDSON, 1880 5X5X24 STONE- CHISELED X, GLO WITNESSES STANDING  
OCRC WITNESS: 1 1/2" PIPE W/ 3/4" IRON IN TOP  
18" ELM N67°W 58.6' PP S70°W 65.6 PP S70°E 78.7  
LCRC #100034 H. PAGE, PS 13591 FOUND ENGINE VALVE OVER 1/2" IRON- SET MON BOX.  
TP S60°E 78.87  
PP S60°W 58.88  
REBAR IN CONC MARKER N71°W 90.78  
FACE CONC MARKER S19°E 95.82  
LCRC# 100244 J. CAMPBELL, PS 15397 FOUND ENGINE VALVE IN MON BOX  
P POLE S50°W 59.04  
ROW POST N65°W 90.62  
P POLE S65°E 78.87

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner**

FOUND ENGINE VALVE IN MONUMENT BOX AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.**

M-13 SE CORNER, SECTION 36, T14N, R18W  
ENGINE VALVE IN MONUMENT BOX  
40d SPK W FACE GUY POLE N11°E 118.13 EDM  
PK NAIL N FACE GUY POLE N73°E 76.18 EDM  
PK NAIL S FACE POWER POLE S65°E 78.83 EDM  
20d SPK SE FACE POWER POLE S57°W 58.88 EDM  
CENTER CONC PROJ MARKER N73°W 90.6 EDM



Signed by J. Randolph Hepworth Date October 6, 1993  
Surveyor's Michigan License No. 26457

11-5-93