

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF -:	LOCATED IN -:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.	T. 15 N. R. 18 W.	M-1; M-2; M-3
2. PROPERTY CONTROLLING IN SECTION	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER _____

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 9, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- M-1 Accepted 1/2 rod for four twp. corners as recovered by MSHD and checked their witnesses; ok as listed under item C.
- M-2 Reestablished 1/4 corner to Sec. 1 (T15N-R18W) & Sec. 6 (T15N-R17W) on line between sec. corners to N & S and at double the distance across sec. corner & 1/8 corner fence to S, and sec. corner & 1/8 line fence to N.
- M-3 Accepted 1" pipe for sec. corner to Sec. 1 & 12 (T15N-R18W) & Sec. 6 & 7 (T15N-R17W) as recovered by MSHD and checked their witnesses; okay as listed under item C.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-1	M-2	M-3
Fd. 1/2" iron rod by old wood fn. post w/sheet metal on N side, 150' W of top of creek ravine	Set DNR monument & cedar post 12" W. Pine N80°E 113.80	Fd. 1" pipe slanted to SW over stone
29" Twin Oak N15°E 26.14	48" Maple S75°E 102.90	26" Maple S65°E 71.76
7" Oak N50°E 29.41	16" Cherry S50°W 61.62	31" Maple S35°W 59.99
3" W. Pine N50°W 40.25	Old cor. Fn. post (Fences N'ly & E'ly) is 28' N & 10' W	51" Maple S75°W 70.88

SIGNED BY Carl F. Roser DATE 5-23-79

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____



SURVEYOR'S MICHIGAN REGISTRATION NO. _____

GOLDEN TOWNSHIP
OCEANA COUNTY