

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 15 N. R. 18 W.	L-1; L-2; L-3
2. PROPERTY CONTROLLING IN SECTION	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 2, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- L-1 Reestablished $\frac{1}{4}$ Sec. 1, T15N-R18W equidistant $\frac{1}{2}$ on line between NE & NW of Sec. 1.
- L-2 Established center of Sec. 1 at intersection of $\frac{1}{4}$ lines. Corner falls in W'ly wheel track of N-S sand trail. Old corner fence Post (fences S'ly and E'ly) is 14'±N and 43'± E.
- L-3 Restored $\frac{1}{4}$ corner from two old county road commission witnesses; 7" SE'ly of SE'ly side of CMP cross culvert. Center E-W gravel road Due S. 2'±. Center gravel road S'ly Due W 1'± on center of sand road to north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-1	L-2	L-3
Set DNR monument & cedar post	Set 3/4"x24" Pipe	Set 1 1/2"x23" Iron Pin, buried in gravel road intersection
8" R. Maple S30°W 29.2	4" W. Pine N50°E 29.9	*30" S. Maple N70°W 79.5
11" Cherry S25°E 23.3	29" W. Pine S05°W 32.5	*26" S. Maple N25°W 80.5
S 1/4 S-36 T16N-R18W	Set cedar post w/loc. tag	13" R. Pine S37°E 52.10
N87°53'W 16.5	Due E 33'	Fd. axle shaft w/gear S73°E 7.74 (buried 8")
⊕ N-S Trail West 28'±		Set ced.post w/loc. tag N45°E 33' (* = old witness)

SIGNED BY Carl F. Roser 5-23-79 DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____ GOLDEN TOWNSHIP
 OCEANA COUNTY

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET