

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY.....	T. N. S. R. E. W.		
2. PROPERTY CONTROLLING IN SECTION 1	T. 15 N. R. 18 W.	1; 2; 3; 5	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.		
4. LOT NO., RECORDED PLAT			
5. PRIVATE CLAIMS			

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 20, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on, 19 found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories established or subsequent re-established~~
 C. (continued)

- 5
- Set 1/2"x3/8"x18" Iron & cedar post
 w/loc. tag
- | | | |
|-------------|-------|-----|
| 5" W. Oak | N10°W | 7.1 |
| 13" W. Oak | N70°E | 5.4 |
| € N-S Trail | Due W | 12' |

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner.
- 1 Established 1/16 corner equidistant & on line between N¼ & NW corner of Sec. 1.
 - 2 Established 1/16 corner equidistant & on line between N¼ & NE corner of Sec. 1.
 - 3 Established 1/16 corner on line between NW corner & W¼ corner of Sec. 1 and at prorated distance to U.S.
 - 5 Established N 1/16 corner on N-S ¼ line of Sec. 1 on line between the N¼ corner and center of Sec. 1 and at proportionate measurement to U.S. per G.L.O. plat.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1	2	3
Set 1/2"x3/8"x21" iron & cedar post w/loc. tag	Set 3/8"x1/4"x16" iron & cedar post w/loc. tag	Set 1/2"x3/8"x19" iron & cedar post w/loc. tag
8" R. Maple S35°E 8.6	8" Twn.R. Pine S55°E 43.5	4" W. Pine N80°W 9.4
6" R. Maple S15°E 14.8	5" R. Pine S10°E 36.1	5" W. Pine N50°E 19.0
W 1/16 on S. line Sec. 36 (16-18) N87°53'W 24.75	SW cor. SE¼ SE¼ Sec. 36 (T16N-R18W) N87°53'W 8.25	5" W. Pine Due S 36.0

SIGNED BY Carl F. Roser DATE 5-23-77

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____



GOLDEN TOWNSHIP
 OCEANA COUNTY