

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 15 N. R. 18 W.	H-5; I-4; I-5
2. PROPERTY CONTROLLING IN SECTION	T. N. S., R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S., R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on Aug. 30, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- H-5 Fd. and accepted 3/4" iron pipe. Apparently previously used and Wit. by RLS#14091.
 - I-4 Fd. and accepted well point for 1/4 Corner; in Ctr. N-S gravel and dirt Co. Rd. and in line with old fence row Easterly.
 - I-5 Fd. & accepted 5/8" rod for Sec. Corner. Fits Stover Survey in Sec. 10 and 1/8 Cor. and 1/4 Cor. to West. Fits approx. Ctr. of roads N-E-W and in line with old tree row to South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-5		I-4		I-5	
Fd. 3/4" iron pipe		Fd. 1 1/4" Well Point		Fd. 5/8" rod	
Power Pole N38°E	65.87	7" R.Pine S20°W	88.16	29" Beech N55°E	96.66
1" Fruit tree S30°E	48.7	8" R.Pine S72°W	35.46	6" R.Pine N70°E	100.81
Ctr.E-W Gr.Rd. Due N	2'+	Set Ced.Post w/Loc.Tag		43" Maple Due S	43.47
Ctr.Gr.Rd. N Due E	3'+	Due W	33'	Fd.well point raised	
Set Ced.Post w/Loc.Tag				w/1/2" pipe N48°27'E	5.88
Due S	16.5			Set Ced.Post	
				w/Loc.Tag Due S	33'


SIGNED BY Carl F. Roser DATE 10-2-78

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____ GOLDEN TOWNSHIP
OCEANA COUNTY