

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 15 N. R. 18 W.	G-3; H-3; I-1
2. PROPERTY CONTROLLING IN SECTION	3, T. 15 N. R. 18 W.	1
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on Aug. 30, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

XX

C. (continued)

1
Set 5/8"X40" rod w/RLS Cap &
Ced.Post w/Loc. Tag
12" W.Ash N05°W 12.7
11" W.Birch S65°E 18.6
W 1/16 on S.Line 34
T16N-R18W N88°16'W 4.95

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- G-3 Found and accepted Conc. Sub'n. type monument at old fence corner, fn's. N-S-E-W. May have been set as a result of Stover survey in Sec. 4.
 - H-3 Re-established 1/4 Cor. in old N-S fence & on line across Sec. Cor. & 1/8 Cor. fence Cor. to E and on line across Sec. Cor. & 1/8 Cor. fence Cor. to West. This position would seem to fit 1885 survey by Hyde reasonably well.
 - I-1 Re-established closing Sec. Corner Comm. to Sec's 2&3 on N. line of T15N-R18W, at record U.S. (G.L.O.) distance east of Standard Cor., 30 links (19.80'). Note: Fd. 3/4" pipe, N70°E, 27.5', as erroneously set & recorded by S. Barnett as I-13, T16N-R18W.
 - 1 Established 1/8 Corner per Std. B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-3	H-3	I-1
Fd. 4" Conc. Mon. & added	Set DNR Mon.& Ced.Post	Set DNR Mon.&Ced.Post
Ced.Post w/Loc. Tag	in old N-S fn.	8" Maple S30°E 30.3
8" Elm S55°W 18.1	7" Cherry Due S 30.1	3" Maple S40°W 32.4
4" Twin W.Birch S05°E 56.9	Ctr Golden Twp. Drain	SE Sec. 34
Ctr. Golden Twp. Drain From E.	Course W'ly Due N 345'+	T16N-R18W N88°16'W 19.80
Due S. 10'+	Corner is in line with road	Fd.3/4"pipe N70°18'E 27.52
Ctr.Golden Twp, -Drain to S.	S'ly, beginning 1/4 mile to	Ctr. N-S Trail Due W. 50'+
Due E. 15'+	South.	


SIGNED BY Carl F. Roser DATE 10-2-78

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____



GOLDEN TOWNSHIP
OCEANA COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. _____