

STATE OF MICHIGAN
 COUNTY OF OCEANA
 RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

3 DEC 1999 2:09:05 PM

For corners in

<u>Oceana</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>15N</u> R <u>18W</u>	<u>G-6</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

JOSEPH E. HERTEN
 REGISTER OF DEEDS

100938

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, J. Randolph Hepworth, in a field survey on October 13 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-6 1/4 CORNER COMMON TO SECTIONS 15 AND 16 T15N, R18W GOLDEN TOWNSHIP

GLO J. Mullett 1838 SET POST 12" Beech S35°E (9 lks) 5.9' 12" Hemlock N65°W (12 lks) 7.9'

Book A, Pg. 198, EM Hyde, 1888; "Found a corner stone previously set 6 inches square 8 inches of which is above the surface." 20" Hemlock S36°W 31' 16" Soft Maple N64°W 19'

Book A, Pg. 200, EM Hyde, 1888; "See #3 Page 199."

Unrecorded Survey, K. Ross #17634, 1/21/77. Set PK over ex. Iron Cen Rd E-W Fence to South PP Due S 48.43' 8" Apple N45°W 70.31'

LCRC# 100256, K Ross #17634, 5/14/80 Set PK over Ex. Iron See Witnesses for Unrecorded Survey 1/21/77

Oceana County Remonumentation
 Peer Group Reviewed & Approved

Date: 11-11-99

JRH
 J. Randolph Hepworth
 Oceana County Surveyor

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

I found a JRH 1/2" Iron and cap which I placed some years ago at the Ross PK Nail position. The Iron is in the centerline intersection of roads E-W and N and on old occupation line to the south. Only one Ross witness is still standing. All Hyde, 1888, witnesses are gone. Upon excavation, I found the JRH Iron to be directly beside a 1" Iron at 12" deep. At 20" deep, I found a 4" square stone beside the 1" Iron. I believe this stone to be the Hyde, 1888, corner.

I accept the Irons and stone as the best available evidence of the position of the original corner. No evidence is known to me that would lead me to believe the corner should be at another location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 4"x20" Harrison Cast Iron Monument, stamped "County Surveyor" and "26457" above the 1" Iron which was driven down.

60d spk	S Face	32" Maple	230°az	112.97'	EDM
60d spk	SE Face	Power Pole	55°az	60.55'	EDM
60d spk	E Face	Power Pole	South	48.58'	EDM
60d spk	NE Face	12" W Pine	114°az	121.70'	EDM



Signed by J. Randolph Hepworth
 Surveyor's Michigan License No. 26457

Date November 30, 1999