

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF OCEANA
RECEIVED FOR RECORD

3 DEC 1999 2:12:39 PM

For corners in

Table with columns: Located In: (Oceana County), Corner Code #, and rows for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

JOSEPH E. NERTEN
REGISTER OF DEEDS

100943

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, J. Randolph Hepworth in a field survey on October 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13, showing a grid of numbers 1-36 with a dot at the intersection of column I and row 6.

A. Description of original monument and accessories and/or subsequent restoration:

I-6 1/4 CORNER COMMON TO SECTIONS 14 AND 15 T15N, R18W GOLDEN TOWNSHIP

GLO J. Mullett 1838 SET POST 12" Beech S48°W (50 lks) 33.0' 12" Hemlock S15°E (25 lks) 16.5'

Book A, Pg. 198, EM Hyde, 1888; "A stone fr wh -a stone bears S48.5°W 46 lks & a stone bears N45°E 79 lks "

LCRC #100256, K. Ross #17634, 1/21/77, Set R/R Spike Cen. Rd E-W,S

- 1) 30" Tw. Willow N60°W 51.17'
2) 12" Maple S30°E 70.53'
3) PP S50°W 85.09'

Unrecorded Survey, JR Hepworth #26457, 5/12/93 Fd R/R Spike

- 2) 16" Maple 156°az 70.54'
3) P pole 246°az 85.12'
4) Rd name sign 228°az 13.22'
5) T pole 72°az 87.38'

Oceana County Ramonumentation
Peer Group Reviewed & Approved

Date: 11-11-99

J. Randolph Hepworth
Oceana County Surveyor

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

I found a RR Spike in the centerline intersection of Roads E-W & S. Occupation line to North begins about 700± North. Corner fits Ross witness of LCRC No. 100256. Two Ross witnesses remain and measure OK. Corner falls in road fill section in excess of 10' above original soil grade. I have no history of this corner between 1888 and 1977. I did not believe any excavation to attempt to locate the Hyde 1888 stone would be beneficial, economical or necessary.

I accept the RR Spike as the best evidence of the position of the original corner. No evidence is known to me that would lead me to believe the corner should be at another location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 4"x20" Harrison Cast Iron Monument, stamped "County Surveyor" and "26457".

Table with columns: Monument Description, Face, Distance, Azimuth, EDM Reading



Signed by [Signature]
Surveyor's Michigan License No. 26457

Date November 30, 1999