

**SURVEY &  
REMONUMENTATION**

JAN 11 1999

**SECTION LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF OCEANA  
RECEIVED FOR RECORD

28 DEC 1998 4:35:46 PM

For corners in  
Oceana

Located In: Corner Code #

JOSEPH E. MERTEN  
REGISTER OF DEEDS

**100878**

1. Public Land Survey	T 15N R 18W	K-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

J. Randolph Hepworth

August 1, 1998

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

K-1 CORNER COMMON TO SECTIONS 1 AND 2 T15N, R18W GOLDEN TOWNSHIP  
GLO SET POST 18" Pine S12°W 11.2' 18" Pine S65°E 31'  
Intersected N. Boundary 33' (50 lk) East of Post (K-13)  
DNR Traverse, Carl Roser #12028, 1976-1979; Set DNR Mon. (closing cor) on line between N 1/4 cor Sec. 2 & NE Cor Sec 1 and at rec. U.S. dist. E.(50 links) of Std. Cor.  
LCRC # 100271, C. Roser #12028, June 26, 1980, Set DNR mon & Cedar Post  
8" R. Oak S35°E 27.3'  
7" B. Oak S10°W 17.9'  
SW Sec 36 (T16N, R18W) N87°53'W 33.0'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.**

I found a 3/4" Pipe with cast-aluminum cap stamped: "Michigan Dept of Conservation - State Forest T15N, R18W, NW COR SEC 1" beside a squared Cedar Post. All DNR witnesses are standing and measure OK. There being no other historical evidence known to me regarding this corner; I accept this as being the best available evidence of the position of the original corner. A newer fence runs east, west and south from this corner.

I accept the 3/4" Pipe as being a careful and faithful re-establishment of the position of the original corner. No evidence is known to me that would lead me to believe that the corner should be at another location.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.**

Found a 3/4" Pipe with cast-aluminum cap stamped: "Michigan Dept of Conservation - State Forest T15N, R18W, NW COR SEC 1". Set 5' Steel Fence Post beside it.

60d spk	E Face	10" B. Oak	202°az	18.18	tape
60d spk	E Face	10" R Oak	152°az	27.87	tape
60d spk	V Face	20" W Oak	82°az	34.91	tape
60d spk	SW Face	20" Oak	300°az	18.54	tape
38' west of W. edge of N-S Ravine					
K-13	T16N Corner	Fd DNR Pipe Monument	west	33.00	tape



Oceana County Remonumentation  
Peer Group Reviewed & Approved

Date: 12-10-98

JRH  
J. Randolph Hepworth  
Oceana County Surveyor

Signed by J. Randolph Hepworth  
Surveyor's Michigan License No. 26457

Date December 21, 1998