

SURVEY & REMONUMENTATION

OCT 27 1993

COMMISSION

**OCEANA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
COUNTY OF OCEANA
RECEIVED FOR RECORD

100509

'93 OCT -7 P2:45

For corners in

OCEANA
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 15N R 18W K-6
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Janet E. Mertens
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, J. Randolph Hepworth in a field survey on September 27, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-6 1/4 CORNER COMMON TO 13 & 14 GOLDEN TOWNSHIP; T15N, R18W
 GLO SET POST 10" SUGAR MAPLE S63°W 10.6' 6" BEECH S72°E 20.5'
 BOOK A- 413 HA GRANT; APRIL, 1896 STONE 17"x6"x5"
 OCRC WITNESS: AXLE SET IN OLD WOOD STAKE; PRE-1950
 12" ELM N8°30'W 44.0'
 TEL POLE S62°W 67.9'
 POWER POLE N60°E 47.20
 TEL POLE N45°W 49.95 NUT ON TOP OF TEL BOX

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner

FOUND RAILROAD SPIKE AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

K-6 1/4 CORNER COMMON TO 13 & 14; T15N, R18W
 SET "COUNTY SURVEYOR" HARRISON 4"x20" CAST IRON MONUMENT IN PLACE OF FOUND RAILROAD SPIKE.

CENTERLINE OF PAVEMENT E - S & NE

60d SPK	N FACE	POWER POLE	N90°E	52.16	EDM
60d SPK	NW FACE	POWER POLE	N33°E	217.37	EDM
60d SPK	SW FACE	TEL POLE	N47°W	49.43	KDM
CENTER	ROAD NAME SIGN POST		S38°W	65.9	EDM
60d SPK	E FACE	10" LOCUST	S16°W	130.09	EDM

Signed by *J. Randolph Hepworth*
 Surveyor's Michigan License No. 26457



Date September 30, 1993

11-5-93