

SURVEY & REMONUMENTATION

OCEANA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE

100530

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FEB 25 1994

STATE OF MICHIGAN COUNTY OF OCEANA

COMMISSION FOR CORNERS OF--

LOCATED IN--

CORNER CODE NUMBER

- 1. PUBLIC LAND SURVEY... T. 15 N. S. R. 15 W. G-7
2. PROPERTY CONTROLLING IN SECTION... T. S. R. E. W.
3. MISCELLANEOUS PROPERTY IN SECTION... T. S. R. E. W.
4. LOT NO. , RECORDED PLAT
5. PRIVATE CLAIMS

'93 DEC 14 A10:25

Jeff E. Martin REGISTER OF DEEDS

REGISTER OF DEEDS STAMP AND FILING NUMBER

J. Randolph Hepworth

I, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 23, 1993, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on, 19, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Oceana County Remonumentation Peer Group Reviewed & Approved Date: 11-18-93

J. Randolph Hepworth Oceana County Surveyor

G-7 CORNER COMMON TO SECTIONS 15, 16, 21, AND 22 LEAVITT TWP; T15N, R15W

GLO SET POST 6" SPRUCE N76°W 9.2' 8" SPRUCE S14°E 6.6' BOOK A-450 HC SALISBURY, DEC 1807 LARGE ROUND STONE WITH POINTED STONE ON TOP (NO WITNESS) OOCR WITNESS: ABOUT 1952 POINTED STONE N END OF FENCE

LCRC #100287 HEPWORTH, LS26457 MARCH 18, 1981 SET 5/8" IRON BESIDE LARGE ROCK-THOUGHT TO BE SALISBURY CENTER ROAD E & N 12" MAPLE SE 18.92 10" TW CHERRY SW 3.07 SE COR OLD SCHOOLHOUSE NW 84.3

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner

FOUND 10" WIDE, 14" LONG, 18" HIGH STONE WITH POINTED RIDGE, PROJECTING FROM GROUND ABOUT 2". AFTER EXCAVATION, FOUND TO BE ON TOP OF A 12"-16" ROUND STONE ABOUT 18" BELOW SURFACE OF GROUND: I BELIEVE THIS STONE TO BE THE SALISBURY CORNER; AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

FOUND 5/8" IRON PER LCRC #100287 WAS ESTABLISHED USING IMPROPER PROCEDURES AND IS NOT UTILIZED IN THIS SURVEY.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

G-7 CORNER COMMON TO SECTIONS 15, 16, 21, AND 22 LEAVITT TWP; T15N, R15W

SET "COUNTY SURVEYOR" HARRISON 4"x20" CAST IRON MONUMENT IN PLACE OF FOUND POINTED STONE AND ON TOP OF THE ROUND STONE. PLACED THE 10"x14"x16" STONE ON THE EAST SIDE OF THE HARRISON MONUMENT AND PLACED THE LARGE TRIANGULAR STONE THAT WAS BESIDE THE #100287 CORNER ON THE WEST SIDE OF THE HARRISON MONUMENT.

LCRC #100287 CORNER IS 2.72' SOUTH AND 6.00' WEST AND HAS BEEN PHYSICALLY REMOVED.

Table with 6 columns: Monument Description, Bearing, Distance, and Tape. Includes items like 60d SPK SE FACE, PK NAIL W FACE, 8" TW CHERRY, POWER POLE, etc.

SIGNED BY [Signature] DATE November 26, 1993

SURVEYOR'S MICHIGAN REGISTRATION NO. 26457

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY [Signature] DATE [Blank] CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY [Signature] DATE [Blank] MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. [Blank]

