SURVEY & REMONUMENTATION

JAN 1 1 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN COUNTY OF OCEANA RECEIVED FOR RECORD

28 DEC 1998 4:34:45 PM

For corners in		The same of the sa
Oceana	Located In: Corner Code #	JOSEPH E. MERTEN
(County)	and and the	REGISTER OF DEEDS
1. Public Land Survey	15N 15W H-5 TR TR TR	100872
Property Controlling in Section Miscellaneous	TR S TR S TR S TR	
Property in Sec.	S TR	Register of Deeds Stamp & File Number
4. Lot No, Reco	orded Plat	
E Private Claime		

	lo, Recorded Plat te Claims				
conforma United St that the o Board of	ndolph Hepworth in a field survey cents of P.A. 74, Michigan P.A. of 1970, the conce with regulations and rules therefore as requates Department of the Interior, Bureau of Lancorner points mentioned in lines 3, 4 and 5 about Land Surveyors or by a Decree of a Court, found as expressed below:	uired in tr d Manage ive were !	ne curre ement o la confo	nt manua: r by a dec rmance w	ree of a Court of Law and /or with the rules of the Michigan
NOTE:	Not more than 2 corners, all in the same to on this certificate.	own and	l range	, may be	recorded

1	Ą	В	C	Ø	E	F	G	H	I	J _}	(1	<u>. M</u>
1	Γ	T	T		T	Τ	T	Т	[,]
2	-	6-	╁	- 5-	╁	4-	+-	· j	 	Ž	-	\vdash
3	_		4-	-		┼	╀	┿	 		 	
4	_	- 7	+	- 8 	+	ا —و ا	}	-10	1-1	! 	<u> </u>	2
5	-	╁╌		+		┼─	╁	•	\vdash	-	一	
6		1,8—	╁	-1/7-	+	16—	╀	15-	-1	4	l-i	3
7			╁	+		┿	+	+-	┼		-	-
8	-	19-	-	-20-	+-	21-	╀-	-22	 _2	3	2	4
9		╀	╀	-	+-	┼-	╀	+	╂		-	
10		30-	+	-29-	╬	28-	╁-	-27	- 2	6	2	5-
11	<u> </u>	+	+-	+	+-	┼-	╂-		-		-	\vdash
12	<u> </u>	31	+	_32_	+	3 <mark>3</mark>	+	-34	 —₃	5	 3	6—
12		L.,				_		$oldsymbol{\perp}$		<u> </u>	<u> </u>	Щ

A. Description of original monument and accessories and/or subsequent restoration: H-5 1/4 CORNER COMMON TO SECTIONS 10 AND 15 T15N R15W LEAVITT TOWNSHIP

14" Hemlock for section post

Book A, Pg 112; S. Edson, 1880; "A conical shaped boulder 12" long and 8 by 4 wide with smaller ones on the West side."

Book A. Pg 324; H. Grant, 1893; "Cedar stake fr. wh. cast iron S. 2"

LCRC # 100287, R. Hepworth #26457, 4-8-81; Set 1/2" IR Ex 1/2" X 4" Bar W 15.7' 24" Maple SE 45.45' 12"Cherry ENE 121.35'

30" Maple WNW

162.05

Unrecorded survey, K. Ross, PS17634, May 8, 1992; File No. 92155S Found 1/2" capped Rebar (bent) replaced w/ 1/2" rebar in c/l road 20" Maple S35°E 45.41 NE Cor. Building South 84 NE Cor. Building South 84.85

NW Cor. Building S32°W 93.45

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

I found a 1/2" Rebar without a cap as described by Ross. Comer falls 3' South of center of E-W Road. No occupation exists to the North or South. This position was re-established by me in 1981 using measurements to 1/16 line occupation. A search of the vicinity failed to yield any other evidence

I accept the 1/2" Iron as a careful and faithful re-establishment of the position of the original corner. No evidence is known to me that would lead me to believe that the corner should be at another location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

Set 4"x20" Harrison Cast Iron M 60d spk NE Face 60d spk S Face 60d spk S Face NW Cor. House Foundation NE Cor. House Foundation	24" Maple 16" Cherry 36" Maple Oceana County Ren Peer Group Reviews	16" Cherry 78°az			J. RANDOLPH HEPWORTH LAND SURVEYOR NO.
Signed bySigned by	J. Randolph Hepword Oceana County Sur		Date	cember	21, 1998