

REMONUMENTATION

FEB 25 1994

COMMISSION

Oceana County Remonumentation  
Peer Group Reviewed & Approved

Date: 11-18-93

OCEANA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE

100527

J. Randolph Hepworth  
Oceana County Surveyor

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF OCEANA

OCEANA (County)	Located In:	Corner Code #
Public Land Survey	T <u>15N</u> R <u>15W</u>	<u>L-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

'93 DEC 14 AIO:25

*Joseph E. Melton*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

J. Randolph Hepworth, in a field survey on November 23, 1993, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as pressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

L-7 1/4 CORNER COMMON TO SECTIONS 13 AND 24 LEAVITT TWP; T15N, R15W  
GLO SET POST 6" CEDAR S41°W 11.9'  
BOOK A-387 HA GRANT JULY, 1895 STAKE 7" CEDAR N39°E 12.5'  
24" ELM N5°W 137'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner

This corner falls in a gravel road running through a swampy region. No witnesses remain from historical record. An ancient fence runs to the east from this corner. I projected this fence from a point about 400' east and recovered several old fence posts in varying state of repair to the center of the gravel road. This represents the best available evidence for the position of the corner.

I SET A 1/2" X 2' IRON IN THE CENTER OF NORTH-SOUTH GRAVEL ROAD ON OLD FENCE LINE TO EAST AND IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

L-7 1/4 CORNER COMMON TO SECTIONS 13 AND 24 LEAVITT TWP; T15N, R15W  
SET "COUNTY SURVEYOR" HARRISON 4"X20" CAST IRON MONUMENT IN PLACE OF SET 1/2" IRON  
60d SPK N FACE 18" WILLOW S87°E 133.16 EDM  
60d SPK NW FACE 8" WILLOW N10°E 331.62 EDM  
60d SPK N FACE 10" WILLOW S66°E 63.90 EDM  
60d SPK SE FACE 20" WILLOW N40°E 261.88 EDM  
CENTER OF LARGE CULVERT NORTH 261' EDM



Witnessed by *J. Randolph Hepworth*  
Surveyor's Michigan License No. 26457

Date November 26, 1993