

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

100533

COMMISSION

STATE OF MICHIGAN

FOR CORNERS OF-- LOCATED IN-- CORNER CODE NUMBER
1. PUBLIC LAND SURVEY... T. 15 N. 8., R. 16 SE. W. C-7
2. PROPERTY CONTROLLING IN SECTION... T. S., R. E. W.
3. MISCELLANEOUS PROPERTY IN SECTION... T. S., R. E. W.
4. LOT NO., RECORDED PLAT
5. PRIVATE CLAIMS

'93 DEC 14 AIO:26

J. Randolph Hepworth REGISTER OF DEEDS

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, J. Randolph Hepworth, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 22, 1993, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law.

Oceana County Remonumentation Peer Group Reviewed & Approved

Date: 11-18-93

A. C-7 CORNER COMMON TO SEC 17, 18, 19 & 20 ELBRIDGE TWP T15N, R16W

Table with 3 columns: GLO SET POST, NO WITNESSES RECITED, CORNER NOT DESCRIBED. Includes entries for BOOK A-78, A-80, A-216 and various survey records.

J. Randolph Hepworth Oceana County Surveyor

OCRC WITNESS, 4-3-88; STONE WITH AXLE ON EAST SIDE
2" J PINE S10°W 49.10 2" R PINES25°W 53.50 36" ELM S45°W 56.1 24" MAPLE S60°E 80.9

HEPWORTH, 8-11-83; I searched and did not find a monument at this location. Because of Road construction, any early corners would be about 15'-20' below existing road pavement surface.

I SET A 1/2"X2" IRON ON 8-11-83 IN CENTERLINE E-W ROAD & OCCUPATION LINE TO THE SOUTH, NO OCCUPATION IS VISIBLE TO NORTH; USING OCRC WITNESSES TO PINE TREES. NO WITNESSES WERE TAKEN ON 8-11-83.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner

Found the 1/2" X2" IRON by Hepworth in the center of the east-west pavement. THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

C-7 CORNER COMMON TO SEC 17, 18, 19 & 20 ELBRIDGE TWP T15N, R16W

SET "COUNTY SURVEYOR" HARRISON 4"X20" CAST IRON MONUMENT IN PLACE OF FOUND 1/2" IRON. C/L E-W ROAD; OCCUPATION LINE TO SOUTH.

Table with 6 columns: Monument description, Face, Distance, Bearing, Monument type. Includes entries for 60d SPK, 8" R PINE, 8" TW CHERRY, 4" ELM.

SIGNED BY [Signature] DATE November 24, 1993

SURVEYOR'S MICHIGAN REGISTRATION NO. 26457

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY CHIEF OF SURVEY PARTY DATE

APPROVED AND SIGNED BY MICHIGAN REGISTERED LAND SURVEYOR DATE

SURVEYOR'S MICHIGAN REGISTRATION NO.

