

**SURVEY &
REMONUMENTATION**

JAN 11 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

100861
STATE OF MICHIGAN
COUNTY OF OCEANA
RECEIVED FOR RECORD

28 DEC 1998 4:33:04 PM

JOSEPH E. NERTEN
REGISTER OF DEEDS

For corners in

<u>Oceana</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>15</u> N R <u>16</u> W	I-4
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

J. Randolph Hepworth May 21, 1998
I, _____, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

I-4 Quarter Corner Common to Sections 10 & 11 T15N, R16W Elbridge Township

GLO SET POST 10" Sugar N30°W 15' 12" Sugar N88°E 18'

OCRC	WITNESS BOOK	Pre-1958	"T" Iron post
8" Elm	W.	36.2'	
R. E. A. Pole	N45°E	92.8'	
Butternut	Due W.	60.5'	

LCRC#	100446, R. Hepworth #26457, 1-25-91	Set 1/2" X 2' Iron
	Center Roads N-S & E	Old occupation line to W
	P Pole	75°AZ 85.85'
	Sign Post	278°AZ 20.85'
	Tw 16" Maple	20°AZ 126.18'
	Tel J. Box Stake	145°AZ 55.5'

Oceana County Remonumentation
Peer Group Reviewed & Approved

Date: 10-13-98

JRH
J. Randolph Hepworth
Oceana County Surveyor

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

I found in the centerline of a north-south road and in the centerline of a road to the east and on an old occupation line to the west a JRH 1/2" Iron and cap at the surface as described in LCRC No. 100446. All OCRC witnesses are gone. This corner was re-established by me in 1991 by the collateral local evidence. Road bed is in a fill/cut transition area. No other ferrous metal stake was detected. I accept this iron as best available evidence of the position of the original corner. No information is known to me that would lead me to believe that the corner should be at another location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

Set a 4"x20" Harrison Cast Iron Monument, stamped "County Surveyor" and "26457" above the JRH Iron which was driven down.

60d spk	SE Face	Power Pole	70°az	85.86	EDM
60d spk	SE Face	10" Ash	12°az	161.12	EDM
60d spk	NE Face	8" Oak	327°az	51.58	EDM
center		road name sign post	277°az	20.96	EDM

Signed by J. Randolph Hepworth
Surveyor's Michigan License No. 26457

Date November 10, 1998

