

**SURVEY &
REMONUMENTATION**

OCT 27 1993

COMMISSION

OCEANA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF OCEANA
RECEIVED FOR RECORD
100506
'93 OCT -7 P2:45

For corners in

<u>OCEANA</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>15N</u> R <u>17W</u>	<u>H-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Joseph E. Mertens
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, J. Randolph Hepworth September 27, 1993
in a field survey on _____, 19_____,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

A. H-7 1/4 CORNER COMMON TO SEC. 15 & 22 HART TWP T15N, R17W
GLO SET POST 10" LYNN N07°W 33.7' 16" BEECH S52°W 26.4'
BOOK A - 3 S. EDSON, MAY 1879 20" STONE & CROCKERY PLACED AT GLO CORNER FOUND, NO WITNESS
BOOK A-130 S. EDSON 1882 CORNER NOT DESCRIBED OR WITNESSED
OCRC WITNESS BOOK: 4-10-51 WELL POINT
10" ELM N05°E 18.3' 8" ELM N45°W 42.0'
NAIL TOP OF S FENCE POST 36.0' NAIL TOP OF FENCE POST 29.80'
LCRC # 100162 D. SOUTH, LS 20623 12-17-73 FOUND PK NAIL IN ROAD @ OCRC WITNESS
STEEL PIPE FENCE POST S. 33.99' CAP IN TOP OF FENCE POST N 29.80
CAP IN SE SIDE PPOLE SW 183.70 4' UP C/L END OF 48" CMP NE 76.60

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner

FOUND 1/2" IRON REPLACEMENT OF D. SOUTH PK NAIL AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE
POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

H-7 1/4 CORNER COMMON TO SEC. 15 & 22 HART TWP T15N, R17W
SET "COUNTY SURVEYOR "HARRISON 4"X20" CAST IRON MONUMENT IN PLACE OF FOUND 1/2" IRON
60d SPK S FACE 4" ELM N72°W 181.41 EDM
R/R SPK N FACE POWER POLE S76°W 184.51 EDM
60d SPK W FACE POWER POLE S54°E 99.87 EDM
CENTER OF CORNER STEEL FENCE POST S02°W 34.00 TAPE
SMALL NAIL/CAP LS20623 TOP OLD WOOD POST N05°E 31.19 -POST LEANS 1.6' NORTH
W&W 1/2" IRON SOUTH 32.95 TAPE



Signed by *J. Randolph Hepworth* Date September 30, 1993
Surveyor's Michigan License No. 26457

11-5-93