

# SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF OCEANA  
RECEIVED FOR RECORD

100575

95 JAN -4 P3:24

For corners in

OCEANA

(County)

Located In:

Corner Code #

- |                                    |                         |       |
|------------------------------------|-------------------------|-------|
| 1. Public Land Survey              | T 16N R 15W             | E-8   |
|                                    | T _____ R _____         | _____ |
|                                    | T _____ R _____         | _____ |
|                                    | T _____ R _____         | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
|                                    | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____ | _____ |
|                                    | S _____ T _____ R _____ | _____ |

*Joseph E. Miller*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

J. Randolph Hepworth, in a field survey on September 1, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

E-8 1/4 CORNER COMMON TO SECTIONS 20 and 21 T16N,R15W COLFAX TWP

GLO SET POST 12" Beech N50°W 15.2' 10" Maple S34°E 18.5'

USFS, R. Griffin, PS, 1975; "Found 1/2" Iron in pavement centerline. Location checks with old witnesses SW. In line with old fence East. HC Salisbury, 1932 Cedar Stake.

4" B Oak West 53.28 24" Pine Stump S43°W 65.12 2" B Oak S49°W 74.00  
8" S. Maple S45°E 90lk 24" Pine Stump S45°W 97lk

No other historical records are known to me.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner

I found a 1/2" Iron 3" below the surface in the center of a north-south asphalt road. This Iron measures 2658.35' south of Corner E-7; and measures 2625.39' north of E-9 corner. Area to southwest has been heavily timbered in recent years. About 150' east, I could detect small pieces of old barb wire of old fence not visible. No occupation lines are distinctly visible; but, this is approximate location of change in land use to the east. Origin of this 1/2" Iron is unknown. Only 1 Griffin witness is still standing.

No evidence is know to me that would lead me to believe that the corner should be at another position. The 1/2" Iron is ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

E-8 1/4 CORNER COMMON TO SECTIONS 20 and 21 T16N,R15W COLFAX TWP

SET "COUNTY SURVEYOR" HARRISON 2 3/4"X20" CAST IRON MONUMENT over the top of the found 1/2" Iron  
60d spk NW Face 3" W Oak 233°az 51.28 EDM  
60d spk N Face 6" B Oak 272°az 53.03 EDM  
60d spk NW Face 8" Sassafras 332°az 89.09 EDM  
60d spk N Face 50" Maple 96°az 113.26 EDM  
60d spk NE Face 8" Cherry 151°az 123.52 EDM

Oceana County Remonumentation  
Peer Group Reviewed & Approved  
Date: 8-18-94

*J. Randolph Hepworth*  
J. Randolph Hepworth  
Oceana County Surveyor

Signed by \_\_\_\_\_ Date November 7, 1994

Surveyor's Michigan License No. 26457

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

