

# SURVEY & REMONUMENTATION

APR 25 1995

## LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF OCEANA  
RECEIVED PER [unclear]

100576

95 JAN -4 P3:24

For corners in **COMMISSION**  
**OCEANA**

	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>16N</u> R <u>15W</u>	E-9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*Joseph E. Matthews*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, J. Randolph Hepworth, in a field survey on September 1, 1994, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**  
E-9 CORNER COMMON TO SECTIONS 20, 21, 28, 29 T16N, R15W COLFAX TWP

GLO SET POST 10" Beech N76°E 21.8'      10" Maple S66°W 31.7'

Information from USFS; R. Griffin, PS: HC Salisbury- Iron rod with glass  
Govt Beach NE 50lks      24" Pine Stump West 109lks

ACT 74, LCRC No. 100373; Hepworth, PS26457; 5-20-88; Set 1/2" x 2' Iron in the centerline of a north-south Road and trace of old fence line to East  
8" R Pine 48°az 117.90      8" Cherry 82°az 86.53  
Stop Sign 252°az 52.5      6" tw Maple 311°az 94.98

No other historical records are known to me.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner**

I found a 1/2" Iron/cap (Hepworth, RLS 26457) in the surface and center of a north-south asphalt road and gravel road to the west. A trace of an old fence line lying down is to the East. This corner was re-established by me in 1988 using the collateral evidence just described. No GLO evidence exists. This corner measures 2625.39' south of E-8 corner and measures 2654.48' north of E-10 corner.

No evidence is know to me that would lead me to believe that the corner should be at another position. The 1/2" Iron is ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.**

E-9 CORNER COMMON TO SECTIONS 20, 21, 28, 29 T16N, R15W COLFAX TWP

SET "COUNTY SURVEYOR" HARRISON 2 3/4"X20" CAST IRON MONUMENT above the found 1/2" Iron

60d spk SW Face	10" Tw Maple	307°az	94.98	EDM
60d spk S Face	10" Tw R Oak	281°az	97.60	EDM
60d spk SE Face	8" Tw Cherry	45°az	86.50	EDM
60d spk S Face	12" R Pine	79°az	117.85	EDM
60d spk N Face	24" R Oak	262°az	173.94	EDM

Oceana County Remonumentation  
Peer Group Reviewed & Approved

Date: 8-18-94

*JRH*  
J. Randolph Hepworth  
Oceana County Surveyor



Signed by *J. Randolph Hepworth*

Date November 7, 1994

Surveyor's Michigan License No. 26457