

5

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 15 N. R. 18 W.	H-1
2. PROPERTY CONTROLLING IN SECTION 3	T. 15 N. R. 18 W.	3; 10
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on Aug. 30, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- H-1 Re-established N 1/4 Cor. Sec. 3, T15N-R18W, equidistant and on line between the NW & NE Cor. of Sec. 3.
- 3 Reluctantly accepted the SE Corner of recorded Sub'n. plat, "Lake Michigan Shores" per C.M. Stover Survey 1953. Stover shows a distance of 5511' for E. line of Sec. 4 & we measured 5492'. The reason for accepting Stover's 1/8 Cor. is that to set it pro-rated to U.S. for 1-mile would be wild, as the NE&SE cor's. of Sec. 4 may well not be the original govt. Cor's. as U.S. returned a distance of 5306' on line between Sec's. 3&4.
- 10 Estab. S 1/8 Cor. on West line of Sec. 3 equidistant & on line between the W 1/4 and SW Sec. 3.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-1	3	10
Set DNR Mon. & Ced. Post	Fd. & accepted conc. plat Mon.	Set 5/8"X40" re-rod w/RLS Cap
12" Maple S20°W 48.4	added Ced. post w/Loc. Tag	& Ced. Post w/Loc. Tag
8" Ash S40°E 63.5	7" Maple S40°W 4.8'	5" Hemlock
S 1/4 Sec. 34	5" Hemlock S65°E 14.8'	in clump of 4 S40°W 11.3
T16N-R18W N88°16'W 9.90'	Ctr. N-S trail Due W 78'	8" Maple S30°E 6.0

SIGNED BY Carl F. Roser 10-2-78 DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE

MICHIGAN REGISTERED LAND SURVEYOR



GOLDEN TOWNSHIP
OCEANA COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. _____