

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 16 N. R. 18 W.	H-13; I-13
2. PROPERTY CONTROLLING IN SECTION	T. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	34 T. 16 N. R. 18 W.	664'-S #10 **664'-N G-13
4. LOT NO.	RECORDED PLAT	
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on Aug. 30, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on Sept. 14, 1978, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- H-13 Re-established S 1/4 Cor. Sec. 34, equidistant and on line between SE & SW Cor's. of Sec. 34.
- I-13 Re-established Sec. Corner Comm. to Sec's. 34&35, on South Line of T16N-R18W; at position That S. Barnett intended to set it per his survey of Sec's. 34&35. (The E 1/2 mile of So. Line S-35 equals the W 1/2 mile of So. Line S-35) and on line between the recovered S 1/4 Cor. S-35 & SW Cor. S-34.
- ** Established NW Corner of S 1/2-SW 1/4-SW 1/4 of S-34 on line between 1/4 Cor. N. & Sec. Cor. S. & 664.07-N. of sd. Sec. Cor. Corner falls in Ctr. of N-S Bit. Rd.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13 <u>S 1/4 34</u>	I-13 <u>SE 34</u>	**
Set DNR Mon. & Ced. Post	Set DNR Mon. & Ced. Post	Drove R.R. Spk
14" Maple N85°W 49.3'	6" W.Oak N65°W 2.5'	3" W.Pine N50°E 52.2
2" Maple N10°W 29.6'	5" Maple N25°E 26.2	5" Maple S45°E 37.0
N 1/4 S-3	NE Sec. 3	Set Ced. Post w/Loc. Tag
T15N-R18W S88°16'E 9.90	T15N-R18W S88°16'E 19.80	Due E 33'
	Fd. 3/4" pipe N79°15'E 46.50	
	Ctr. N-S trl. Due W 30'+	
	Ctr. E-W trl. Due S 250'+	


SIGNED BY Carl F. Roser DATE 10-2-78

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____



PENTWATER TOWNSHIP
OCEANA COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. _____