

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

| FOR CORNERS OF --: | LOCATED IN --: | CORNER CODE NUMBER |
|---------------------------------------|-------------------|--------------------|
| 1. PUBLIC LAND SURVEY | T. 16 N. R. 17 W. | B-9; B10; B-11 |
| 2. PROPERTY CONTROLLING IN SECTION | T. S. R. E. W. | |
| 3. MISCELLANEOUS PROPERTY IN SECTION | T. S. R. E. W. | |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 24, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- B-9 Fd. 1/2" rod in mon. box, & line with fence to S. Fits Highway data prior to new road construction.
- B-10 Fd. & accepted conc. mon. for center of Sec. 30, by Nordlund & Dunlap. Approx. position of old fence corner remains N, S & E is Due W 17'±.
- B-11 Found 4" square concrete monument. Fits MSHD witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| B-9 | B-10 | B-11 |
|-------------------------------|--|--|
| Fd. 1/2" iron rod in mon. box | Fd. 4" round conc. mon. w/1/2" rerod; added ced.post | Fd. & accepted 4" sq. conc. mon. w/1/2" rerod; added cedar post w/loc. tag |
| NE corner store fdn. | w/loc. tag | |
| S35°W 110.3 | 20" W. Oak N65°W 35.97 | 15" R. Oak N55°W 19.01 |
| NW corner store fdn. | 19" W. Oak N05°W 35.53 | 12" R. Oak N25°E 27.40 |
| S45°W 130.0 | 8" W. Pine S75°W 17.35 | 11" R. Oak N55°E 41.40 |

SIGNED BY Carl F. Roser 5-14-80 DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

WEARE TOWNSHIP
OCEANA COUNTY