

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 16 ^{N.} R. 18 ^{W.}	K-9; L-9; M-9
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S. R. _____ E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above were, in a field survey on June 26, 1979, established re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-9 Fd. conc. mon. that fits two 1929 C. Stover wits., survey of record at Co. Surveyor's Office, Hart - Liber A, page 479.
- L-9 Fd. & accepted RLS Sammy Barnett's N $\frac{1}{2}$ corner of Sec. 25. Corner falls in 26" of water in muskrat marsh.
- M-9 Fd. pointed stone; and steel fence post by Highway Department. Corner is in 10" of water in open marsh.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-9	L-9	M-9
Fd. 4" round conc. mon. w/1/2" rerod & added ced. post w/loc. tag	Fd. 1"x42" pipe; replaced w/1 1/4"x11' pipe; added ced. post w/loc. tag	Fd. steel fn. post & pointed stone in marsh; added DNR mon. & ced. post w/loc. tag
18" W. Oak N05°E 28.47	SW cor. of SW'ly 2'x5' conc. bridge wingwall	N'ly edge Rv. Due S 28.4'±10'
2-9" W. Oak N45°W 8.84	N03°16'E 437.4	E'ly edge Rv. Due W 237'±10'
4" W. Pine N60°E 36.86		Q US-31 B.R. 690'

SIGNED BY Carl F. Roser 5-14-80 DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:


SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)



SURVEYOR'S MICHIGAN REGISTRATION NO. _____

PENTWATER TOWNSHIP
OCEANA COUNTY