

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

| FOR CORNERS OF-- | LOCATED IN-- | CORNER CODE NUMBER |
|--|--|--------------------|
| 1. PUBLIC LAND SURVEY----- | T. _____ N. _____ E. _____ S. _____ R. _____ W. _____ | ----- |
| 2. PROPERTY CONTROLLING IN SECTION <u>25</u> | T. <u>16</u> N. _____ E. _____ S. _____ R. <u>18</u> W. _____ | <u>12; 13; 14</u> |
| 3. MISCELLANEOUS PROPERTY IN SECTION----- | T. _____ N. _____ E. _____ S. _____ R. _____ W. _____ | ----- |
| 4. LOT NO.-----, RECORDED PLAT----- | ----- | ----- |
| 5. PRIVATE CLAIMS----- | ----- | ----- |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 26, 1979, established re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 12 Established S 1/8 on N-S 1/4 line, Sec. 25, equidistant and on line between fd. 1 1/4" pipe at S 1/4 corner and S Barnett's center of section.
- 13 Set 5/8"x40" rerod for center of SE 1/4 of Section 25.
- 14 Established S 1/8 corner on E line of Sec. 25 per standard B.L.M. instructions. Corner falls in 10" of water in swamp.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| 12 | 13 | 14 |
|---|---|---|
| Set 5/8"x40" rerod w/RLS cap 4" R. Oak N55°E 33.70 | Set 5/8"x40" rerod w/RLS cap & cedar post w/loc. tag | Set 1"x7 1/2" pipe w/RLS cap & cedar post w/loc. tag |
| 6" W. Oak S50°E 28.07 | 14" R. Pine N80°E 6.97 | SW'ly side Rv. N01°E 159'±3' |
| Set ced. post w/loc. tag Due E 33' | 3" W. Pine S40°W 2.22 | SW'ly side Rv. S88°E 90'±3' |
| Fd. 1 1/4" well pt. S30°54'E 27.61 | | |
| Ctr. N-S trail Due E 2'± | | |

SIGNED BY Carl F. Roser 5-14-80 DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:


SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)



SURVEYOR'S MICHIGAN REGISTRATION NO. _____

PENTWATER TOWNSHIP
OCEANA COUNTY