

OCT 27 1993

COMMISSION

STATE OF MICHIGAN
COUNTY OF OCEANA
RECEIVED FOR RECORD

OCEANA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

100494

'93 OCT -7 P2:44

For corners in

OCEANA
(County)

Located in:

Corner Code #

- 1. Public Land Survey T 16N R 18W K-7
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

James E. Martins
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, J. Randolph Hepworth, a field surveyor on September 28, 1993

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-7 CORNER COMMON TO SEC 13, 14, 23 & 24 PENTWATER TWP T16N, R18W
 GLO SET POST 10" HEMLOCK N79°E 58.1' 12" HEMLOCK S53°W 16.5'
 OCRC: 4" CONC. MONUMENT FENCE LINE TO N. - 23' SOUTH OF. (COR?)
 RECORDED PLAT - FOREST HILLS
 RECORDED PLAT - PLAT 'D' OFFICIAL MAP VILLAGE OF PENTWATER
 RECORDED PLAT - PLAT 'A' OFFICIAL MAP . . . SECTION 24
 RECORDED PLAT - SUNSET VIEW; SEC 24-16-18
 LCRC #100443 R HEPWORTH, PS 26457 FOUND CONC. MONUMENT SET SPIKE OVER
 TEL POLE S73°W 90.26 TEL POLE N58°W 32.76
 P POLE S43°E 35.30 32" MAPLE N08°W 24.40

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner

FOUND 4" CONC. MONUMENT AS PER LCRC 100443 AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

K-7 CORNER COMMON TO SEC 13, 14, 23 & 24 T16N, R18W
 COUNTY SURVEYOR HARRISON'S 120" DIRT POLE REPLACED IN PLACE OF FOUND 4" CONC. MONUMENT

PK NAIL	N FACE	TEL POLE	S73°W	90.26	TAPED
60d SPK	SW FACE	TEL POLE	N58°W	32.76	TAPED
60d SPK	SW FACE	P POLE	S43°E	35.30	TAPED
60d SPK	E FACE	32" MAPLE	N08°W	24.40	TAPED



Signed by *J. Randolph Hepworth*
Surveyor's Michigan License No. 26457

Date September 30, 1993

11-5-93