

SURVEY & REMONUMENTATION

OCT 27 1993

COMMISSION

STATE OF MICHIGAN
COUNTY OF OCEANA
RECEIVED FOR RECORD

100495

'93 OCT -7 P2:44

**OCEANA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>OCEANA</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>16N</u> R <u>18W</u>	<u>L-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Joseph E. Martin
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, J. Randolph Hepworth, in a field survey on September 28, 1993

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-7 1/4 CORNER COMMON TO SEC 13 & 24 PENTWATER TWP T16N, R18W
 GLO SET POST 24" W PINE N10°E 21.1' 6" W PINE S35°W 31.0'
 BOOK A - 370 HA GRANT, JUNE, 1894
 18" GRATE BAR 9" HENLOCK N62°E 10.9' 4" PINE S32 1/2°E 19.1'
 OCRC WITNESS = MDOT WITNESS
 LCRC # 100053 MDOT FD 1"X3"X1 1/2" GRATE BAR
 19" OAK N10°E 17.67' 28" OAK N50°W 33.78' 10" MAPLE S30°E 26.29'
 LCRC # 100443 R. HEPWORTH, LS 26457 1-7-91 FD GRATE BAR
 28" OAK N10°E 17.62
 10" TW BIRCH N80°W 27.87
 14" TW OAK S40°E 48.95
 12" MAPLE S25°E 26.29

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner

FOUND 1"X3"X1 1/2" GRATE BAR AS PER LCRC #100053 AND #100443 AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

L-7 1/4 CORNER COMMON TO SEC 13 & 24 PENTWATER TWP T16N, R18W
 SET "COUNTY SURVEYOR" HARRISON 4"X20" CAST IRON MONUMENT ON TOP OF FOUND 1"X3"X1 1/2" GRATE BAR

60d SPK E FACE	28" OAK	N10°E	17.62	TAPED
60d SPK NE FACE	14" TW OAK	S40°E	48.95	TAPED
60d SPK NE FACE	12" MAPLE	S25°E	26.29	TAPED
60d SPK NE FACE	16" MAPLE	S15°E	43.88	TAPED
60d SPK NE FACE	36" OAK	N50°W	33.78	TAPED



Signed by J. Randolph Hepworth
 Surveyor's Michigan License No. 26457

Date October 6, 1993