

SURVEY & REMONUMENTATION

OCT 27 1993

COMMISSION

OCEANA COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF OCEANA
 RECEIVED FOR RECORD
100493
 '93 OCT -7 P2:44

For corners in
OCEANA
 (County)

Located in: _____ Corner Code # _____

J. E. Mertens
 REGISTER OF DEEDS

1. Public Land Survey	T <u>16N</u> R <u>18W</u>	<u>M-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

J. Randolph Hepworth September 28, 1993

I, _____, in a field survey on _____, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-7 CORNER COMMON TO SEC 13 & 24 PENTWATER TWP T16N, R18W
 GLO SET POST 24" W PINE S70W 42.9' 6" BEECH N27°W 12.5'
 BOOK A- 370 HA GRANT JUNE, 1894
 PD 1/2" X 36" IRON SET BY J. BEAN IN 1882 NO WITNESSES RECITED
 LCRC # 100054 CARLSON, MDOT 5-11-70 PD 1/2" X 4" IRON
 13" MAPLE N55°W 36.07 13" MAPLE N05°E 30.37
 13" TW MAPLE N75°E 2.18 16" OAK SOUTH 60.72
 PA 132 SURVEY: JACKET #358 R HEPWORTH, RLS 26457 8-19-83
 PD ANCIENT 1/2" IRON, FITS MDOT WITNESSES

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner

FOUND ANCIENT 1/2" IRON AS PER LCRC #100054 AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

M-7 SEC COR. COMMON TO 13 & 24; T16N, R18W & SEC 18 & 19; T16N, R17W
 SET "COUNTY SURVEYOR" HARRISON 4" X 20" CAST IRON MONUMENT ON TOP OF FOUND 1/2" IRON

C/L E-W GRAVEL ROAD SOUTH 20 FEET
 60d SPK NE FACE 16" MAPLE N55°W 36.07 TAPE
 60d SPK E FACE 18" MAPLE N05°W 30.37 TAPE
 60d SPK N FACE 13" TW MAPLE N75°E 2.18 TAPE
 60d SPK E FACE 20" OAK SOUTH 60.36 TAPE



Signed by *J. Randolph Hepworth*
 Surveyor's Michigan License No. 26457

Date October 6, 1993

11-5-93